

Planning Application for the Aylesbury Estate Regeneration

# Masterplan & First Development Site Application

# Utility Infrastructure Report

**WSP** 







mæ



**WSP** 









# Appendix 5.1 Framework Construction Environmental Management Plan (CEMP)

This framework CEMP provides a document structure for mitigating likely significant environmental effects during the demolition and construction works. The CEMP will be further developed and implemented on a site specific basis by the contractors appointed to carry out the works prior to construction works commencing in response to appropriate planning conditions.

### Contents

- Introduction project overview key issues and considerations.
- Method Statement and logistics plan.
- Site Management and resources.
- Programme.
- Health & Safety.
- Travel plan overview, liaison with LB Southwark and the Police, constraints, routes, parking of vehicles.
- Deliveries Loading and unloading of plant and materials.
- Storage of plant and materials used in constructing the development.
- A secure and safe site boundary.
- The control of dust during demolition and construction.
- The control and monitoring of noise.
- Waste Management recycling and disposal of waste.
- Public space protection of the public.
- Security.
- Fire Prevention fire strategy during construction.
- Environmental Policy.
- Considerate Constructors Policy.



# Appendix 5.2 Framework Code of Construction Practice (CoCP)

This framework CoCP follows the Southwark Council Environmental Code of Construction Practice (Reference 5.1) and provides a document structure for the required control measures and the standards to be implemented across the Estate throughout the project to ensure that existing and new residents and businesses are protected from environmental impact during the construction phase of the adjacent new development.

The CoCP will be further developed and implemented on a site specific basis by the contractors appointed to carry out the works prior to construction works commencing in response to appropriate planning conditions. .

### Contents

- Preliminary
  - Information on site activities
- Safety and Security
  - Hoardings etc
  - Gates
  - Scaffolding, Gantries
  - Crane Arcs
  - Security
  - Lighting
  - Good Housekeeping

### Site Activities

- Noise and Vibration
- Piling
- Sand Blasting
- Dust and Air Pollution
- Demolition of Existing Structures
- Asbestos
- Lead
- Polychlorinated Biphenyls (PCBs)
- Demolition Waste Removal
- Contaminated Land Investigation
- Water Pollution
- Archaeology
- Urban Ecology
  - Protection of Trees
  - Tree replacement

Project number: 50600304 Dated: 01/09/2014

Revised:

- Encroachment into Wildlife Areas
- Protection of River Corridors and Wetland features
- Lorry Movements
- Roads and Footpaths
- Mud on Roads
- Skips
- Control of Construction Site Run Off
- Rodent Infestations
- Finishes and Maintenance Works
- The Considerate Contractor Scheme





Project number: 50600304 Dated: 01/09/2014 Revised:



# AYLESBURY ESTATE REGENERATION

Utility Infrastructure Report

15/08/2014

# **Quality Management**

Issue/revision	Issue 1	Revision 1	Revision 2
Remarks	DRAFT	FINAL DRAFT INTERNAL AND CLIENT/LEGAL REVIEW	
Date	15/08/2014	5/9/2014	
Prepared by	Wayne Fortune	Wayne Fortune	
Signature			
Checked by	Alastair Edwards	Alastair Edwards	
Signature			
Authorised by	Alastair Edwards	Alastair Edwards	
Signature			
Project number	50600304	50600304	
Report number	140815 Aylesbury Estate Utilities Planning Application Report_DRAFT	140905 Aylesbury Estate Utilities Planning Application Report_PLANNING ISSUE	
File reference	\\ser01brm1uk\buildings\\ Projects\2464\1_Project s\50600304 - Aylesbury\C Documents\Post BAFO\Rpts\Utilities Planning Report	\\ser01brm1uk\buildings\\ Projects\2464\1_Project\ s\50600304 -\ Aylesbury\C\ Documents\Post\ BAFO\Rpts\Utilities\ Planning Report	

Project number: 50600304 Dated: 15/08/2014 Revised: 05/09/2014

# **Aylesbury Estate Regeneration**

# **Utility Infrastructure Report**

15/08/2014

### Client

Notting Hill Housing Trust

### Consultant

Wayne Fortune WSP UK 7 Lochside View Edinburgh EH12 9DH UK

Tel: +44 020 7314 5000 Fax: +44 20 7314 5111

www.wspgroup.co.uk

## Registered Address

WSP UK Limited 01383511 WSP House, 70 Chancery Lane, London, WC2A 1AF

### **WSP Contacts**

Wayne Fortune

e-mail: Wayne.Fortune@WSPgroup.com

Alastair Edwards

e-mail: Alastair.Edwards@WSPgroup.com

Mark Searle

e-mail: Mark.Searle@WSPgroup.com



# **Table of Contents**

1	Executive Summary	5
2	Introduction	6
3	Utility Infrastructure Strategy	7
4	Existing Utility Infrastructure	8
5	Network Alterations	15
6	New Supplies	19
7	Approach to Phasing	24
8	Conclusions	26

### **Appendices**

Appendix 1 – First Development Site Utility Survey Results

Appendix 2 – Masterplan Correspondence and Drawings

Appendix 3 – First Development Site Correspondence and Drawings

Project number: 50600304 Dated: 15/08/2014 Revised: 05/09/2014

# 1 Executive Summary

This report provides a summary assessment of the existing utility infrastructure within and in proximity to the site boundary of the proposed Aylesbury Estate regeneration project.

The report considers the Masterplan and First Development Site separately.

The Masterplan considers Phases 2, 3 and 4 and Site 10/Plot 18 of the project and the First Development Site considers Phase 1 of the project - Sites 1b/1c.

Consultation has taken place with each of the Utility Companies owning and operating the infrastructure services networks within and surrounding the site of the proposed development to determine the extent of works required to retain and/or adapt the networks to accommodate the requirements of the development.

The consultation process is ongoing and the following key elements have been established to date:

- Reinforcement of the existing electricity network is not currently required to accommodate the Masterplan based on the response received from UKPN. For the Masterplan, 2 No. new supply cables will be provided from spare panels UKPN's main substation located off-site at Verney Road.
- Connections to the existing Intermediate Pressure (IP) gas network are required to provide the required gas load for the proposed Energy Centres to provide the heating and hot water requirement for the Masterplan and the First Development Site. Southern Gas Networks have confirmed that network reinforcement is not currently required.
- Initial feedback from Thames Water has confirmed that there is insufficient capacity within the existing potable water network to support the Masterplan at full build out. This will be confirmed on receipt of the results from an on-going network modelling exercise.
  - On completion of the network studies, Thames Water will look at what works are required to potentially avoid laying new trunk mains within the development.

These measures could include, for example, off-site reinforcement, rezoning supplies and connection into alternative pressure systems.

For the purposes of this report, the First Development Site is considered in greater detail with C4 budget costs and quotations obtained for identified utility diversions and new supplies respectively.

The C4 budget costs, quotations and drawings for the First Development Site provide a 'snap shot' on the current strategy for enabling and servicing the proposed site. The coordination of the routes and the phasing of the utilities works (new supplies and diversions) to support the First Development Site are subject to on-going development through detailed design.



### 2 Introduction

WSP Power Systems has been commissioned by Notting Hill Housing (NHH) to undertake a study to assess the existing utility infrastructure within and in proximity to the site boundary of the proposed Aylesbury Estate regeneration project.

The statutory undertakers have been contacted to confirm the location of their assets in relation to the application site. This base information has been, and will continue to be, augmented by a series of intrusive and non-intrusive surveys completed in key areas to validate record information obtained during the course of developing the Masterplan.

The report reviews the existing utility networks to understand the extent of network modifications generated by the development proposals and assesses the ability of the existing electricity, gas, telecommunications and potable water networks to support the additional network loads.

This report provides a summary of the existing utility infrastructure within the application site (and surrounding area) and outlines the proposed utility strategy for the proposed development.

The report considers the Masterplan and First Development Site separately, whereby the Masterplan considers Phases 2, 3 and 4 and Site 10/Plot 18 of the project and the First Development Site considers Phase 1 of the project - Sites 1b/1c.

For the purposes of this report, the First Development Site is considered in greater detail with C4 budget costs and quotations obtained for identified utility diversions and new supplies respectively.

The C4 budget costs, quotations and drawings for the First Development Site provide a 'snap shot' on the current strategy for enabling and servicing the proposed site. The coordination of the routes and the phasing of the utilities works (new supplies and diversions) to support the First Development Site are subject to on-going development through detailed design.

Similarly, the information provided in this report pertaining to the site wide masterplan is subject to refinement and further development when each site comes forward for detailed design.

This report does not cover the foul and surface water sewer systems (refer WSP Flood Risk Assessment document) or the Energy Strategy (refer WSP Energy Assessment and District Heating Study) which are covered by separate documents.

Project number: 50600304 Dated: 15/08/2014 Revised: 05/09/2014

# 3 Utility Infrastructure Strategy

WSP have consulted utility stakeholders to identify required network alterations to accommodate the masterplan proposals.

Diverting utility infrastructure to accommodate land development is a regular occurrence within the industry. Further consultation and surveys will be required to confirm the scopes of work for required network alterations in line with statutory requirements.

The network alterations are described in Section 5.

An assessment has been carried out, in the form of a load profiling exercise, to understand the load growth for the application site and to assess the impact on the existing utility infrastructure networks. Load profiling provides an estimate of the maximum peak utility demand.

Utility stakeholders have been consulted in order to assess the impact of the demands on existing networks.

The regulatory regimes under which public service supply companies operate dictate that any network expansion results in no loss or reduction of service to existing customers.

WSP have consulted with the supply companies and will therefore ensure the minimum regulatory standards are maintained.

Utility services will be supplied from existing networks with new supplies distributed throughout the application site below ground and arranged in accordance with National Joint Utilities Group (NJUG) guidelines.

New supplies are described in Section 6.



# 4 Existing Utility Infrastructure

WSP have obtained utility record information for statutory undertaker apparatus within the application site and the surrounding area. The following companies own and operate the existing utility networks:

Electricity UK Power Networks (UKPN)

Gas Southern Gas Networks (SGN)

Water Thames Water (TW)

**Communications** Openreach, Virgin Media (VM), Vodafone

Other 3, Orange, T-Mobile (Mobile Communications Base Stations)

Non-intrusive surveys, in the form of an underground service mapping survey (including Ground Penetrating Radar) have been completed for the First Development Site to determine the approximate line and level of existing below ground utilities.

At the time of writing, intrusive surveys, in the form of excavating slot trenches to determine the location of utilities, are underway within the First Development Site to determine the location of existing services at strategic points throughout the site.

Drawing records of the underground service mapping survey completed for the First Development Site are located in Appendix 1.

### Masterplan

### **Electricity**

Electricity supplies to the existing building stock are provided from the UKPN 11kV network and are distributed throughout the site via high voltage (HV)/ low voltage (LV) substations and LV substations which are typically located at ground floor level within the existing building stock.

The existing infrastructure also serves customers beyond the application site.

Extra high voltage (EHV) circuits operating above 11kV are noted within the existing footways/carriageways within the application site.

### Gas

Low pressure (LP) gas mains [various sizes/materials] are located throughout the application site and provide supplies to the existing building stock. The mains are routed within the existing footways/carriageways.

There are no Medium Pressure (MP) mains within the application site save for the short section serving the existing Energy Centre as noted below.

The existing infrastructure also serves customers beyond the application site.

An intermediate pressure (IP) main is routed through the application site in both the footway and carriageway. The IP main provides a connection to the existing Energy Centre via an IP/MP Pressure Reduction Station (PRS).

### **Potable Water**

Distribution mains [various sizes/materials] are located throughout the application site and provide supplies to the existing building stock. The mains are routed within the existing footways/carriageways.

The existing infrastructure also serves customers beyond the application site.

Project number: 50600304 Dated: 15/08/2014

Revised: 05/09/2014

### **Telecommunications**

Below ground ducts/chambers and above ground cabinets are located throughout the application site and provide connections to the existing building stock for both Openreach and VM.

The existing infrastructure also serves customers beyond the application site.

Vodafone have a route through the application site, connections to the existing building stock are to be confirmed.

Mobile communications base stations are noted within the application site.

### **District Heating**

District heating mains are distributed from the Energy Centre located adjacent to Thurlow Street (on Inville Road) to thermal substations located within the existing building stock.

Secondary mains provide connectivity to end point connections. The majority of mains are routed within the existing footways/carriageways with some being located on above ground structures.

### First Development Site

### **Electricity**

Electricity supplies to the existing building stock are provided from the UKPN 11kV network.

A HV/LV substation (Boyson Road Bradenham 90057) is located within the Bradenham block. Further, LV substations are located within the Chartridge 77 to 105 block (Westmoreland Rd Chartridge 90434) and Chiltern block (Portland Street Chiltern 90319).

HV and LV cables are routed below ground through the site (and external to the site in Albany Road, Bradenham Close, Westmoreland Road and Portland Street) between the above mentioned on-site substations and other off-site substations.

The existing infrastructure also serves customers beyond the application site.

An extra high voltage (EHV) circuit operating above 11kV is noted in the footway/carriageway of Portland Street.

### Gas

A 150mmØ Ductile Iron (DI)/4"Ø Cast Iron (CI) LP main is routed adjacent to the Bradenham block from Albany Road to Westmoreland Road.

A 100mmØ DI/150mmØ DI LP main is routed adjacent to the Chiltern block from Albany Road to Westmoreland Road.

Further to the above, there are 100mmØ DI/4"Ø DI mains routed throughout the site, a 12"Ø CI LP main located in the footway/carriageway adjacent to the site in Albany Road and an 75mmØ/90mmØ Polyethylene (PE) LP main in the footway/carriageway of Westmoreland Road.

Supplies to the existing building stock are taken from the mains routed adjacent the Bradenham and Chiltern blocks and from the 100mmØ DI/4"Ø DI mains routed throughout the site

The existing infrastructure also serves customers beyond the application site.

### **Potable Water**

A 180mmØ High Performance Polyethylene (HPPE) distribution main is routed in Bradenham Close, passes through the walkway at the north end of the Bradenham block and continues in Westmoreland Road and then crosses Portland Street and continues off-site. The distribution main is generally routed in the carriageway.



A 125mmØ HPPE distribution main is connected to the above mentioned 180mmØ HPPE main and is routed into the site via the walkway through the Chartridge 1-68 block and terminates adjacent to the Chartridge 120-149 block. The distribution main is generally routed in the carriageway.

Further to the above, there are 2 No. 250mmØ HPPE mains routed in the carriageway of Albany Road.

Supplies to the existing building stock are taken from the 125mmØ, 180mmØ and 250mmØdistribution mains.

The existing infrastructure also serves customers beyond the application site.

### **Telecommunications**

### Openreach

Openreach have below ground fixed telecommunications networks (chambers and ducts) located in Albany Road, Bradenham Close, Westmoreland Road and Portland Street.

Chambers and ducts are routed adjacent to the Chiltern block and provide connectivity between the duct routes in Albany Road and Westmoreland Road and an associated cabinet in Westmoreland Road.

Duct routes are located throughout the site providing connectivity to the existing building stock.

Openreach have confirmed the duct routes contain both copper and fibre cables.

The existing infrastructure also serves customers beyond the application site.

### Virgin Media

Virgin Media (VM) have below ground fixed telecommunications networks located in Bradenham Close, Westmoreland Road and Portland Street.

There are 2 No. major cabinets located in the existing verge of Westmoreland Road.

Chambers, ducts and cabinets are routed adjacent to Chartridge 1-68 block and provide connectivity between the duct routes in Bradenham Close and Westmoreland Road. Further, chambers, ducts and cabinets routed adjacent to Chartridge 77-105 and 120-129 blocks provide connectivity between the duct route in Bradenham Close and a road crossing over Albany Road serving 235 Albany Road.

The duct routes and cabinets located within the site provide connectivity to the existing building stock.

Virgin Media have confirmed the duct routes contain both coaxial and fibre cables.

The existing infrastructure also serves customers beyond the application site.

### Mobile Communications

There are 2 No. Orange mobile telecommunications base stations (Ref: GLN0191) located on the Chiltern block within the First Development Site.

### **District Heating**


The existing district heating mains are routed to the site from the Energy Centre and enter the First Development Site via Portland Street. District heating pipework is located on a pipe bridge which crosses Portland Street between Gayhurst and Chiltern blocks.

Primary district heating mains are routed to thermal substations in Chiltern, Bradenham and Chartridge blocks with secondary district heating mains providing supplies to the existing building stock.


Project number: 50600304

Dated: 15/08/2014 Revised: 05/09/2014

### Extract from UKPN record mapping [part FDS shown]




### Extract from SGN record mapping






### Extract from TW potable water record mapping



### Extract from Openreach record mapping



Project number: 50600304 Dated: 15/08/2014 Revised: 05/09/2014

### Extract from VM record mapping



### Location of mobile communications base stations





### Extract from District Heating record mapping



14

Project number: 50600304 Dated: 15/08/2014 Revised: 05/09/2014

### 5 Network Alterations

A desktop review of utility infrastructure services has been conducted and consultation with utility stakeholders is now at an advanced stage in understanding the impact of the proposals on existing utility infrastructure.

Further consultation and surveys will be required to establish scopes of work for required network alterations and to confirm routes for diverted infrastructure services.

As the First Development Site is considered in greater detail, estimates and quotations have been obtained for network alterations. The scope, coordination of the routes and the phasing of the diversions are subject to ongoing development through detailed design.

The following outlines the proposed network alterations required to accommodate the proposed Aylesbury Estate regeneration project.

Key correspondence and drawings for the Masterplan are located in Appendix 2 and in Appendix 3 for the First Development Site.

### Masterplan

### **Electricity**

HV and LV networks located within the site boundaries will be abandoned and removed ahead of demolition/construction works.

It will be necessary to establish temporary HV/LV substations to serve retained off-site circuits from the existing substations located within the existing building stock which will need to be decommissioned and removed ahead of demolition. Off-site retained circuits are to be transferred to the location of the permanent substations constructed and commissioned to support the application site on completion.

HV and LV diversions will also be required to accommodate future construction and proposed alterations to the existing footway/carriageway layout.

EHV circuits EHV 313 (66kV) and EHV 386 are to be diverted to accommodate the current proposals. It is prosed to divert these circuits south in Kinglake Street and into Thurlow Street.

During consultation, UKPN have expressed the opinion that EHV circuits M19A and M25, which are located in Alsace Road, are thought to be idle. It will be necessary for UKPN to carry out further surveys to confirm this and whether or not diversions will be required.

### Gas

LP gas mains and supplies located within the site boundaries will be abandoned and removed ahead of demolition/construction works.

LP diversions will also be required to accommodate future construction and proposed alterations to the existing footway/carriageway layout.

The IP main routed through the application site will require to be protected/diverted to accommodate the proposed landscaping strategy.

The IP connection to the PRS and the PRS associated with existing Energy Centre will be removed when the Energy Centre is decommissioned and removed from site.

### **Potable Water**

Distribution mains and supplies within the site boundaries will be abandoned and removed ahead of demolition/construction works.

Diversion of the existing distribution mains will also be required to accommodate future construction and proposed alterations to the existing footway/carriageway layout.



### **Telecommunications**

Below ground ducts/chambers and above ground cabinets (Openreach and VM) within the site boundaries will be abandoned and removed ahead of demolition/construction works.

Diversion of below ground ducts/chambers will also be required to accommodate future construction and proposed alterations to the existing footway/carriageway layout.

Vodafone have a below ground fixed telecommunication network (chambers and ducts) located in the footway adjacent to Plot 18 and Phases 3 and 4 which may need to be altered to accommodate proposed alterations to the existing footway/carriageway layout.

The existing mobile communications base stations noted within the application site are to be relocated prior to demolition/construction.

### **District Heating**

District heating mains located within the site boundaries will be abandoned and removed ahead of demolition/construction works.

Diversion of district heating mains may also be required to accommodate future construction and proposed alterations to the existing footway/carriageway layout.

### First Development Site

### **Electricity**

It will be necessary to establish a temporary substation in the location of the Chartridge 1-68 block to allow existing off-site circuits from the Boyson Road Bradenham 90057 substation to be retained during demolition and construction works.

Existing circuits (HV and LV) will be transferred to the temporary substation ahead of decommissioning and removing the Boyson Road Bradenham 90057 substation. The Boyson Road Bradenham 90057, Westmoreland Rd Chartridge 90434 and Portland Street Chiltern 90319 substations are to be decommissioned and removed ahead of demolishing the existing building stock.

In order to remove the existing HV and LV cables routed through the site it will be necessary to provide new HV circuits in Westmoreland Road and Bradenham Close and provide new LV circuits in Westmoreland Road, Portland Street, Bradenham Close and Albany Road.

A new LV circuit is required in Bradenham Close/Albany Road to maintain connectivity to Ellison House.

Further, alterations to existing circuits are required to accommodate new footway/carriageway layouts surrounding the site.

The EHV circuit located in the footway/carriageway of Portland Street is affected by the current footway/carriageway layout and will require to be diverted/protected.

Existing service disconnections, including removal of meters, are to be completed ahead of demolition.

### Gas

The 150mmØ DI/4"Ø CI and 100mmØ DI/150mmØ DI LP mains routed adjacent to the Bradenham and Chiltern blocks will be cut and capped in Albany Road and Westmoreland Street prior to demolition. The 100mmØ DI/4"Ø DI mains routed throughout the site are to be abandoned prior to demolition.

To facilitate the above it will be necessary to provide a new 180mmØ PE LP main in Portland Street between Albany Road and Westmoreland Road. Further, a new 180mmØ PE LP link is required in Camberwell Road between the existing 180mmØ PE LP mains located either side of the existing footway/carriageway.

Alterations to the existing 12"Ø CI and 75mmØ/90mmØ PE LP mains in Albany Road and Westmoreland Road are required to accommodate the new footway/carriageway layouts surrounding the site.

Project number: 50600304 Dated: 15/08/2014

Revised: 05/09/2014

Existing service disconnections, including removal of meters, are to be completed ahead of demolition.

### **Potable Water**

The 180mmØ HPPE distribution main passing through the walkway at the north end of the Bradenham block will be diverted into Bradenham Close.

At this stage, diversion of the 180mmØ HPPE distribution main in Westmoreland Road has been allowed for to accommodate the new footway/carriageway layouts. However, the current location of the main is to be confirmed during intrusive investigation, following which a decision will be made as to whether or not the diversion is required.

The 125mmØ HPPE distribution main which is routed into the site via the walkway through Chartridge 1-68 block and other connections provided from Bradenham Close and Albany Road will be cut and capped prior to demolition.

Alterations to the existing 250mmØ HPPE mains in Albany Road are required to accommodate the new footway/carriageway layouts surrounding the site.

Existing service disconnections, including removal of meters, are to be completed out ahead of demolition.

Existing supplies from Albany Road to Ellison House are to be retained prior to demolition.

### **Telecommunications**

### Openreach

A new below ground chamber and duct route is to be installed in Albany Road/Portland Street to facilitate the diversion of the existing route which passes below the Chiltern block.

The remaining duct routes located throughout the site will be abandoned once the existing building stock is vacated. Openreach will cut and cap the existing incoming cables within the chambers surrounding the site.

Diversions of the chamber and duct routes in Albany Road and Bradenham Close are required to accommodate the new footway/carriageway layouts surrounding the site.

Existing connectivity to Ellison House is to be retained through a cable diversion via Albany Road prior to demolition.

### Virgin Media

New below ground chamber and duct routs are to be installed in Albany Road, Westmoreland Road and Portland Street to facilitate the diversion of the routes located within the site. Two new street cabinets are to be constructed in the southern footway of Albany Road opposite the First Development Site to allow for the necessary cable diversions. VM are in the process of revising their C4 estimate for the site to provide ducts for the necessary diversions in Albany Road south.

As VM have cables pass through the site and serve customers beyond the First Development Site, it is necessary to continue the new below ground chamber and duct route to a point adjacent to the Wendover block (beyond Thurlow Street) and install a new below ground duct route in Bagshot Street to allow for the necessary cable diversions.

The duct routes and cabinets within the site will be abandoned once the existing building stock is vacated and the above diversions are complete.

Alterations to the existing duct routes in Westmoreland Road and Portland Street are required to accommodate the new footway/carriageway layouts surrounding the site.

Virgin Media do not provide connectivity to Ellison House.

### **Mobile Communications**

WSP are aware that negotiations are on-going between the London Borough of Southwark estates team and Orange regarding the relocation of the existing mobile telecommunications base stations.



WSP are not party to current status of the negotiations and are working on the basis that the base stations will be relocated ahead of demolition.

### **District Heating**

The incoming district heating mains, from Portland Street, are to be disconnected at the site boundary once the existing building stock is vacated.

The existing primary and secondary mains will therefore be abandoned and removed as part of the demolition process.

Temporary boiler plant is to be provided for Ellison House to provide heating and hot water supplies prior to demolition.

Project number: 50600304

Dated: 15/08/2014 Revised: 05/09/2014

# 6 New Supplies

An assessment has been carried out, in the form of a load profiling exercise, to understand the load requirement of the application site and to understand the impact on the existing utility infrastructure networks.

It should be noted that the utility networks are dynamic and the responses received from the utility companies are based on the network at the time of the response being issued.

The following details the area/land use schedule and assumptions which form the basis of the load profiling exercise:

### Masterplan

- 2,702 residential units
- Up to 2,500m<sup>2</sup> of employment space
- Up to 1,100m<sup>2</sup> of retail space
- Up to 1,600m<sup>2</sup> of healthcare facilities
- Up to 1,050m<sup>2</sup> of pre-school facilities
- Up to 500m<sup>2</sup> of community space

### First Development Site

- 825 residential units
- A Community Centre

### Assumptions made during load profiling exercise:

- The space heating and hot water supplies in the residential dwellings will be provided from the proposed Energy Centres and their associated District Heating Systems.
- Flats/maisonettes will be provided with electrical cooking appliances and residential units with gas cooking appliances.
- Dedicated cooling for the proposed residential units is not included in the electrical demand calculations.
- The appointed ESCo will confirm the required infrastructure for the export of electricity from the proposed Energy Centres.
- Landlord's electrical loads assumed to account for external feature lighting provision within the site boundary.

Any changes to the area/land use schedule or the assumptions will impact on the findings of this report.

Initial consultation with utility stakeholders is underway in order to assess the impact of the demands and to identify proposed points of connection and any reinforcement works required.

As the First Development Site is considered in greater detail, estimates and quotations have been obtained for new supplies. The coordination of the routes and the phasing of the new supplies to support the First Development Site are subject to on-going development through detailed design.

Loading calculations are to be revisited once the masterplan and mix of units is taken forward to detailed design. Final loads may vary from the initial calculations dependent on the strategy taken forward.

Formal connection applications will be pursued once the scheme is finalised in line with the construction programme.

New supplies will be distributed throughout the application site below ground and arranged in accordance with National Joint Utilities Group (NJUG) guidelines.



As far as reasonably practicable and through agreement with the network operator, the new network will utilise common trenching.

Key correspondence and drawings for the Masterplan are located in Appendix 2 and in Appendix 3 for the First Development Site.

### Masterplan

### **Electricity**

It is anticipated the proposed development will impose a peak load of approximately <u>6,875kW</u> on the existing electrical network.

Initial consultation with UKPN has confirmed that the existing 11kV network currently has sufficient capacity to accommodate the additional load.

UKPN will install 2 No. new supply cables, for the whole Masterplan electrical load, from dedicated feeders fed from spare panels at UKPN's main substation located off-site at Verney Road which is situated approximately 2,500m east of the Masterplan.

A new 11kV network will be required within each development site to provide electricity to the proposed units. Below ground 11kV cables will connect to the existing UKPN network and will be distributed throughout the development and connect to a number of proposed substations.

Each distribution substation will be located at ground level and will either be; housed in a glass reinforced plastic (GRP) enclosure, brick built structure of approximately 3m tall or incorporated into the building fabric in line with UKPN guidance.

Service connections (low voltage circuits) will be provided from the substations to the individual units.

### Gas

It is anticipated that the proposed development will impose a peak load of approximately **25,500kWh** and an annual load of approximately **32,194,050kWh/annum** on the existing gas network.

An Intermediate Pressure (IP) connection will be required to supply the proposed Energy Centre in Phase 2. It will also be necessary to establish a PRS associated with the IP connection to provide gas to the Energy Centre at the required pressure.

Based on the gas requirement for the heating and hot water load for the masterplan including the First Development Site (approximately 31MW), SGN have confirmed that reinforcement is not currently required to the existing IP network. The proposed Point of Connection to the existing gas network and the route to site will be confirmed during detailed design.

A new Low Pressure (LP) network will be required within each development site to provide gas, for cooking purposes, to the proposed houses and non-residential use types. The proposed Point of Connection and route to site will be confirmed during detailed design.

Below ground pipe(s) will connect to the existing SGN network and will be distributed throughout the development.

Service connections will be provided from the LP mains to the individual units.

Reference is to be made to the Energy Strategy for the distribution of the District Heating System supplies.

### **Potable Water**

It is anticipated that the proposed development will impose a peak flow of approximately <u>31.40l/s</u> on the existing potable water network (excluding Fire Fighting Requirements).

Project number: 50600304 Dated: 15/08/2014

Revised: 05/09/2014

Thames Water are currently in the process of completing a network modelling exercise for the Masterplan and First Development Site, the results of which are yet to be received. In consultation with Thames Water, the following is confirmed;

- Thames Water confirm network modelling is required and in progress. Full development should not commence until this exercise is complete.
- Initial feedback is that there is insufficient capacity within the existing network to accommodate the masterplan based on submitted potable water loads.
- On completion of the network studies, Thames Water will look at what works are required to potentially avoid laying new trunk mains within the development.

These measures could include, for example, off-site reinforcement, rezoning supplies and connection into alternative pressure systems.

A potable water distribution network will be required within each development site to provide potable water to the proposed units.

Below ground pipe(s) (distribution mains) will connect to the existing TW network and will be distributed throughout the development.

Service connections will be provided from the distribution mains to the individual units.

### **Telecommunications**

Below ground telecommunications networks (ducts and chambers) will be required within each development site to provide telecommunications connectivity to the proposed units. Above ground street cabinets will also be required. It is anticipated that both Openreach and VM will be approached for proposals.

Below ground ducts will connect to the existing Openreach and VM networks and will be distributed throughout the development.

Connections will be provided from the main telecommunications duct routes to the individual units.

Openreach (on request) will provide a proposal for the required on-site and off-site works once planning permission is granted and 4 weeks ahead of construction beginning on-site. If off-site reinforcement to the Openreach network is required to serve the development this will be carried out at Openreach's cost (up to an agreed value per plot).

Openreach's Walworth Exchange is closest to the application site and is currently under review for providing superfast broadband (Fibre to the Premise FTTP) within the masterplan area. An application will be made to Openreach for FTTP connectivity as each development site comes forward for detailed design.

Further, initial consultation with VM has confirmed that increasing the number of units within the masterplan area should not have a negative impact on the existing network. An application will be made to VM as each development site comes forward for detailed design.

### **District Heating**

A network of primary and secondary mains will be distributed below ground within each development site between the Energy Centre, thermal substations and end point connections.

For further information refer to WSP document Energy Assessment and District Heating Study.

### First Development Site

### **Electricity**

It is anticipated that the First Development Site will impose a peak load of approximately **1,800kW** on the existing electrical network.



The First Development Site will be fed from feeder E2 of the Montford Place B substation by looping in and out between Grosvenor Terrace 93086 and Bethwin Road Boundary House 93021 substations.

HV circuits will be laid from the Point of Connection in Camberwell Road to the First Development Site via Westmoreland Road and Bradenham Close. HV circuits will be distributed within the site between the proposed double substation in Sub-plot 1 and the proposed single substation in Sub-plot 4.

The substations are to be located at ground floor level within the building fabric of Sub-plot 1 and Sub-plot 4. The location of the substations will provide 24/7 unrestricted access for UKPN personnel from the proposed footway/carriageway.

The double substation in Sub-plot 1 will also provide capacity for the retained circuits transferred to the temporary substation prior to demolition. The retained circuits will transferred to the Sub-plot 1 substation prior to the removal of the temporary substation.

LV cables will be distributed below ground within the First Development Site from the Sub-plot 1 and Sub-plot 4 substations to provide connections to the proposed building stock.

### Gas

It is anticipated that the First Development Site will impose a peak load of approximately <u>7,500kWh</u> and an annual load of approximately <u>9,441,900kWh/annum</u> on the existing gas network.

An IP gas main is required to be brought to the site in order to provide the required quantity of gas for the proposed Energy Centre which is to be located within Sub-plot 5. The Energy Centre will supply the heating and hot water requirement for the First Development Site.

A Pressure Reduction Station (PRS) is required to provide gas at the required pressure for the prosed Energy Centre. The PRS will be located within the boundary of Sub-plot 6 and will be visually screened from the adjacent footway/carriageway and surrounding plots.

A new IP main will be laid below ground from the Point of Connection in Wells Way/Albany Road (TBC by SGN during detailed design) to the First Development Site via Albany Road. A low pressure (LP) pipe will be laid below ground from the PRS location at Sub-plot 6 to the Energy Centre in Sub-plot 5.

A new LP network is required to provide gas for to the proposed houses in Sub-plots 2 and 3 and to supply 2 No. catering loads within Sub-plot 1. The Point(s) of Connection to the existing network (assumed from Westmoreland Road and Portland Street) and the proposed routing within the First Development Site are to be confirmed on receipt of a formal SGN quotation.

### **Potable Water**

It is anticipated that the First Development Site will impose a peak flow of approximately <u>11.60l/s</u> on the existing potable water network (excluding Fire Fighting Requirements).

A new potable water distribution network is required to provide individual connections for the proposed houses in Sub-plot 2 and Sub-plot 3 and provide connections to communal locations within Sub-plots 1, 4, 5 and 6. The Point(s) of Connection to the existing network will be from Albany Road, Bradenham Close and Westmoreland Road and routed within the First Development Site.

The proposed connections and route allow for the necessary Fire Fighting connections within the First Development Site.

### **Telecommunications**

### Openreach

A new below ground duct and chamber network is required to provide telecommunications connectivity to the First Development Site. Openreach have prepared initial proposals for the distribution of ducts and chambers throughout the First Development Site.

Project number: 50600304 Dated: 15/08/2014

Revised: 05/09/2014

New street cabinets may also be required to serve the First Development Site, the location and number of cabinets as well as the final routing and phasing of the new below ground duct and chamber network will be confirmed during a pre-construction meeting with Openreach.

The proposed Point of Connection to the existing Openreach network is in Albany Road adjacent to Bradenham Close. Openreach have not confirmed whether or not off-site reinforcement works are required to their existing network to support the First Development Site. Any off-site works will be arranged for by Openreach in line with statutory requirements.

An application has been made to Openreach for FTTP connectivity for the First Development Site. Openreach have confirmed that they should be contacted again two to three months in advance of commencing on-site construction.

### Virgin Media

A new below ground duct and chamber network is required to provide VM telecommunications connectivity to the First Development Site. VM infrastructure is to be incorporated into the First Development Site to provide further choice to end tenants in terms of telecommunications connectivity and to avoid potential future disruption due to VM installing infrastructure following completion of the site and the footways/carriageways being adopted.

VM have prepared initial proposals for the distribution of ducts and chamber and the location of street cabinets throughout the First Development Site. The proposed Point of Connection to the VM network will be to the diverted ducts in Albany Road and relocated ducts in Portland Street. New street cabinets will also be required in Portland Street to serve the First Development Site.

The location and number of cabinets as well as the final routing and phasing of the new below ground duct and chamber network will be confirmed during a pre-construction meeting with VM.

### **District Heating**

A network of primary and secondary mains will be distributed below ground within the First Development Site between the Energy Centre (within Sub-plot 5), thermal substations and end point connections.

For further information refer to WSP document Energy Assessment and District Heating Study.



# 7 Approach to Phasing

The Aylesbury Estate regeneration project will be delivered in four phases over a number of years; as such the proposed phasing will impact of the approach to the provision of new utility supplies to accommodate the proposals.

The routing and phasing of new utility supplies to support the Masterplan and First Development Site are subject to on-going development through detailed design.

This section considers the phasing for the Masterplan and the First Development Site.

### Masterplan

### **Electricity**

UKPN proposed to install 2 No. new supply cables, for the whole Masterplan electrical load (excluding the First Development Site), from their Verney Road main substation. It will be necessary to install these cables from the Verney Road substation to the Masterplan prior to establishing and energising the proposed new substations within Phase 2.

New networks will be extended through phases to allow for connections to the proposed building stock in the following phase (where feasible) in order to minimise off-site disruption.

### Gas

The Intermediate Pressure (IP) connection and construction of a PRS, to serve the Phase 2 Energy Centre, will need to be completed in line with the construction programme and be designed to accommodate the loading required to serve heating and hot water to the Masterplan.

At the time of enquiry, no reinforcement to the existing IP gas network is required to support the gas load required for the Masterplan.

The Low Pressure (LP) network required within each development site may need to be installed ahead of plot construction depending on the final Point of Connection to the existing network.

New networks will be extended through phases to allow for connections to the proposed building stock in the following phase (where feasible) in order to minimise off-site disruption.

### **Potable Water**

The approach to phasing will be determined on receipt of the results from the network modelling exercise.

The potable water distribution network required within each development site may need to be installed ahead of plot construction depending on the final Point of Connection to the existing network.

New networks will be extended through phases to allow for connections to the proposed building stock in the following phase (where feasible) in order to minimise off-site disruption.

### **Telecommunications**

The below ground telecommunications networks (ducts and chambers) required within each development site may need to be installed ahead of plot construction depending on the final Point of Connection to the existing networks.

New networks will be extended through phases to allow for connections to the proposed building stock in the following phase (where feasible) in order to minimise off-site disruption.

Project number: 50600304

Dated: 15/08/2014 Revised: 05/09/2014

### First Development Site

### **Electricity**

The proposed double substation in Sub-plot 1 will be established to provide power for Sub-plots 1, 2, 5 and 6 with a ducted route provided to the single substation in Sub-plot 4 allowing the substations to be linked. The Sub-plot 1 substation will be established and energised prior to the removal of the temporary substation.

LV cables will be distributed below ground within the First Development Site from the Sub-plot 1 and Sub-plot 4 substations, in line with construction phasing, to provide connections to the proposed building stock.

### Gas

The required PRS will be installed and commissioned ahead of Sub-plot 6 construction to provide gas to the Energy Centre in line with the construction programme. The Energy Centre will be constructed as part of Sub-plot 5, e.g. ahead of Sub-plot 6. The PRS, incoming Intermediate Pressure (IP) and outgoing Low Pressure (LP) mains will be installed ahead of plot construction.

The new LP network required to provide gas for to the proposed houses in Sub-plots 2 and 3 and to supply 2 No. catering loads within Sub-plot 1 may have to be installed ahead of plot construction depending on the Point of Connection (assumed to be Portland Street and Westmoreland Road) which is to be confirmed by SGN.

### **Potable Water**

The new potable water distribution network required to provide individual connections for the proposed building stock may have to be installed ahead of plot construction depending on the Point of Connection (assumed to be Albany Road, Bradenham Close and Westmoreland Road) which is to be confirmed by Thames Water.

### **Telecommunications**

### Openreach

Due to the proposed Point of Connection in Albany Road it will be necessary to install ducts and chambers ahead of plot construction. The final routing and phasing of the new below ground duct and chamber network will be confirmed during a pre-construction meeting with Openreach.

### Virgin Media

Due to the proposed Point of Connection in Albany Road and Portland Street it will be necessary to install ducts and chambers ahead of plot construction. The final routing and phasing of the new below ground duct and chamber network will be confirmed during a pre-construction meeting with VM.



### 8 Conclusions

In summary, utility infrastructure has been identified within the application site and the surrounding area.

As the First Development Site is designed in detail it will be necessary to continue consultation with the affected utilities to develop and agree the detailed scopes of work necessary to accommodate the proposals in terms of the required diversions to enable the site and new supplies to the proposed building stock.

The estimates and quotations obtained to date for the First Development Site will be further discussed with the affected utilities and firm orders placed in line with the proposed demolition and construction programmes.

As the Masterplan is developed, and each site comes forward for detailed planning, it will be necessary to reengage with all the affected utilities to acquire detailed estimates and develop scopes of work for the anticipated diversionary works and new supplies to site.

Formal connection applications will be pursued, for the Masterplan, once the scheme is finalised in line with the proposed construction programme.

For the Masterplan and the First Development Site, so far as reasonably practicable, amendments to utility services affected by highway modifications will be carried out at the same time as the highway modifications to minimise disruption to the local community.

The routing and phasing of new utility supplies to support the Masterplan and First Development Site are subject to on-going development through detailed design.

For the Masterplan, as per the First Development Site, intrusive/non-intrusive surveys will be undertaken in key areas to validate record information obtained from affected utility stakeholders. Further investigation will include the following;

- Underground service mapping survey of the development area including ground penetrating radar (GPR) to determine approximate line and level of surveyed utilities.
- Excavation of slot trenches to determine underground utilities within the site as noted on record drawings at strategic points throughout the development.

Project number: 50600304 Dated: 15/08/2014

Dated: 15/08/2014 Revised: 05/09/2014


# Appendices



# Appendix 1

Project number: 50600304 Dated: 15/08/2014 Revised: 05/09/2014









# Appendix 2





Registered Office: Newington House 237 Southwark Bridge Road London SE1 6NP

UK Power Networks (Operations) Limited

Company:

Registered in England and Wales No: 3870728

Mr Wayne Fortune WSP House, 70 Chancery Lane London WC2A 1AF DNQ/NBC/CS/LPN/401520613-201991

01/09/2014

Contacting Us
If you need any help
07875 116539

Dear Mr Wayne Fortune

Re: Budget Estimate for Diversions & New Supplies.

Aylesbury Estate Regeneration, Albany Road, London, SE17 2BJ.

Project Reference Number: 401520613-201991

Thank you for your recent enquiry regarding the above location. I am writing to you on behalf of London Power Networks PLC the licensed distributor of electricity for the above address trading as UK Power Networks.

I am pleased to be able to provide you with a Budget Estimate for the Works described below, Diversions & New Supplies (estimated total load of 6875 KW) at Aylesbury Estate Regeneration, Albany Road, London, SE17 2BJ, NOT including 1B/1C site.

It is important to note that this budget estimate is intended as a guide only. It may have been prepared without carrying out a Design, site visit or system studies. No enquiry has been made as to the availability of consents or the existence of any ground conditions that may affect the works.

### 1. Budget estimate

The budget estimate for this work is:

£7,500,000.00 (exclusive of VAT)

### 2. Budget Estimate summary of the Assumptions and Works:

The Works Described in this letter include for:

- 1. Diversion of HV/LV cables,
- 2. Removal of existing substation,
- 3. Relocation of existing substations to temporary locations,
- 4. Provide 2 new cables supply for the entire development from a UKPN main substation,
- 5. Provision of new permanent substations,
- Provide complete HV and LV Cable installation.

### Works to be carried out by the customer

- Install substations concrete base/plinth, for relocated temporary substations,
- Provide adequate area for the new permanent substations, at no cost to UKPN,
- Excavate and reinstate all trenches on site, with your boundary,
- Earthing for the substation will have to be installed in accordance with UK Power Networks plans.

### Works to be carried out by UK Power Networks

- Decommission and safely remove existing HV substations,
- Decommission and safely temporary remove LV substations,
- Divert HV and LV cables,
- Provide and Install 2 new supply cables from 2 dedicated feeders fed from spare panels at Verney Road MSS, which is about 1.5 miles from the site,
- Supply and Install new permanent substations at new locations to replace existing,
- Excavate and supply/install new duct and cables for the HV circuits,
- Excavate and supply/install new duct and cables for the LV circuits,
- Test and commission new scheme and relocated new substation,
- New Leases will be obtained for the replacement Network substations while the existing are surrendered.

The sites included in this Estimate are: 2A/2B, 3A/3B, 4, 5 & 6, 8 & 9, 10, 11 TO 14, and not 1B/1C.

#### Important Note:

The Capacity requested for this site and the 2 spare panels allocated in this Budget Estimate cannot be reserved.

Please note that if any of the assumptions prove to be incorrect, this may have a significant impact on the price in any subsequent quotation. You should note also that UK Power Networks' formal connection offer may vary considerably from the budget estimate. If you place reliance upon the budget estimate for budgeting or other planning purposes, you do so at your own risk.

If you would like to proceed to a formal offer of connection then you should apply for a quotation, Please refer to our website <a href="http://www.ukpowernetworks.co.uk/internet/en/help-and-advice/documents/the\_connection\_process.pdf">http://www.ukpowernetworks.co.uk/internet/en/help-and-advice/documents/the\_connection\_process.pdf</a> for 'The connection process' which details our application process. To help us progress any future enquiry as quickly as possible please quote the UK Power Networks Reference Number from this letter on all correspondence.

If you have any questions about your budget estimate or need more information, please do not hesitate to contact me. The best time to call is between the hours of 9am and 4pm, Monday to Friday. If the person you need to speak to is unavailable or engaged on another call when you ring, you may like to leave a message or call back later.

Fridge

Yours sincerely

Claude Fridja UK Power Networks Project Manager Major Projects Connections

Newington House 237 Southwark Bridge Road London SE1 6NP

Mobile: 0787 511 6539

E mail: <a href="mailto:claude.fridja@ukpowernetworks.co.uk">claude.fridja@ukpowernetworks.co.uk</a>

was all the water of the way



Registered Office: Newington House 237 Southwark Bridge Road London SE1 6NP

Registered in England and Wales No: 3870728

Company: UK Power Networks (Operations) Limited

Mr Wayne Fortune WSP House, 70 Chancery Lane London WC2A 1AF

7 July 2014

Re: (NTR) Aylesbury Estate Regeneration. Albany Road, London. SE17 2BJ.

**EHV Diversions** 

Project Reference Number: 401555280/208137

Dear Wayne

Thank you for your recent enquiry regarding the above location. I am writing to you on behalf of London Power Networks PLC the licensed distributor of electricity for the above address trading as UK Power Networks.

I am pleased to be able to provide you with a budget estimate for the works, Diversions of the EHV cables.

It is important to note that this budget estimate is intended as a guide only. It may have been prepared without carrying out a site visit or system studies. No enquiry has been made as to the availability of consents or the existence of any ground conditions that may affect the works. It is not an offer to provide the connection and nor does it reserve any capacity on UK Power Networks' electricity distribution system.

#### 1. Budget estimate

The budget estimate for this work is:

£3,000,000.00 (exclusive of VAT)

### 2. Budget estimate assumptions

This estimate is based on the diversion of EHV 313-66kV at the top end of the development area into Thurlow Road and then the diversion of cables into a utility corridor further down Thurlow Road.

The cable is oil filled and we have based the diversion on conecting between existing joint bays.

We combine the two diversions into one single diversion as they meet at the same joint bay in Thurlow Street.

We have assumed that the cables will not go in the utility corridor as we have no details of the utility corridor (e.g. drawings, construction, ownership, rights of access, maintenance etc.) and that the cables will run above the corridor with a suitable depth of cover.

This budget estimate is based on the following assumptions:

Detail design required

non Loudalitems

- Route survey required to confirm proposed route/space in roads
- Circuit identification required to confirm that the cables are New Cross-Southbank 66kV
- Existing cable 66kV, 3 core, FFC, 0.6sq inch. Replacement cable to be 132kV, 1core.XLPE
- Use of by oil by pass pipe rather than installation of tanks at joint bays.
- Hydraulic design required to confirm use of oil by pass.
- Survey required to confirm if adequate space at joint bay locations for 3core FFC-3 x core XLPE joint.
- Diversion between existing joint bays
- Due to route length assumes central joint in XLPE cable
- As slewing of cables will not be allowed the diversion covers the whole length of the site in Thurlow Street.
- Includes diversion required at Northchurch
- Includes diversion in Kingslake Street, but not diversion into a utility corridor.
- · Assumes cables can be run outside utility corridor

Please note that if any of the assumptions prove to be incorrect, this may have a significant impact on the price in any subsequent quotation. You should note also that UK Power Networks' formal connection offer may vary considerably from the budget estimate. If you place reliance upon the budget estimate for budgeting or other planning purposes, you do so at your own risk.

If you would like to proceed to a formal offer of connection then you should apply for a quotation, Please refer to our website <a href="http://www.ukpowernetworks.co.uk/internet/en/help-and-advice/documents/the connection process.pdf">http://www.ukpowernetworks.co.uk/internet/en/help-and-advice/documents/the connection process.pdf</a> for 'The connection process' which details our application process. To help us progress any future enquiry as quickly as possible please quote the UK Power Networks Reference Number from this letter on all correspondence.

If you have any questions about your budget estimate or need more information, please do not hesitate to contact me. The best time to call is between the hours of 9am and 4pm, Monday to Friday. If the person you need to speak to is unavailable or engaged on another call when you ring, you may like to leave a message or call back later.

# Yours sincerely

Claude Fridja UK Power Networks Project Manager Major Projects Connections

Newington House 237 Southwark Bridge Road London SE1 6NP

1.12

Mobile: 0787 511 6539 E mail: <u>claude.fridja@ukpowernetworks.co.uk</u>

Salto

Our Ref: 794625 Your Ref: None given

Wayne Fortune WSP UK Ltd WSP House 70 Chancery Lane London WC2A 1 AF

12/08/2014

Dear Mr Fortune,



SGN Connections Limited St. Lawrence House Station Approach Horley Surrey RH6 9HJ

Tel: 0845 070 1431

# RE: New connection(s) at: Aylsebury Estate Regeneration, Southwark, London SE17 2BJ

Further to your request dated 04/06/2014 regarding the new connection at the above site, please find a budget indication quote detailed below.

**Works to be carried out:** SGN Connections to connect to the existing 6" Steel Intermediate Pressure main in the carriageway of Albany Road & install a new Intermediate pressure main, terminating at inlet of IP/MP governor. From outlet of governor install a new MP PE main to the kiosk location at the energy centre.

Location 6 Budget Indication 15.5MW: £388,400
Location 6 Budget Indication 31MW: £397,600
Location 7 Budget Indication 15.5MW: £493,400
Location 7 Budget Indication 31MW: £505,000

All prices quoted above will be subject to VAT at the appropriate rate,

Please note that this figure is a budget indication only and does not represent an offer to carry out the work. This budget cost is based on the information we have been provided with by you.

We will not be able to complete a firm quotation until a full design study has been carried out. There is a charge to carry out a design study that will provide a more accurate cost for work to be done. Upon receipt of a firm request, we will advise you of the cost for this design study.

Current capacity check indicates that no reinforcement is required however this is subject to change. A contribution from you may be required towards the cost of associated reinforcement works. Upon receipt of a firm request, we will evaluate the actual work required and let you know what those costs are.

It is assumed that no easements or third party permissions are required to carry out all works.

Please note that this budget indication does not take into account for any existing Southern Gas Networks infrastructure that may require diverting. Details of these can be obtained from Southern Gas Networks Diversions/Isolations – 0845 070 3497, or at the following email address: planning&design\_diversions@sgn.co.uk

If you have any further queries relating to this budget indication, please feel free to contact me on the telephone number at the top of this letter.

Yours sincerely,

Kevin Wort Design Assistant


24 hour gas escape number 0800 111 999\*
\*Calls will be recorded and may be monitored


SGN Connections is part of Scotia Gas Networks Registered in England No. 05618886 Registered Office: St. Lawrence House, Station Approach, Horley, Surrey, RH 9H.I


----

www.sgn.co.uk

# Masterplan Diversions








GTs or third parties may also be present in this area but are not shown on this plan. Information with regard to such pipes should be obtained from the relevant owners. No warranties are given with regard to the accuracy of the information shown on this plan. Service pipes, valves, siphons, sub-connections etc are not shown but their presence should be anticipated. You should be aware that a small percentage of our pipes/assets may be undergoing review and will temporarily be highlighted in yellow. If your proposed works are close to one of these pipes, you should contact the SGN Plant Protection Team on 08450703497 for advice. No liability of any kind whatsoever is accepted by SGN or its agents, servants or sub-contractors for any error or omission contained herein. Safe digging practices, in accordance with HS (G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that plant location information is provided to all persons (whether direct labour or sub-contractors) working for you on or near gas apparatus. Information included on this plan should not be referred to beyond a period of 28 days from the date of issue.


# INTRANET MAP VERSION 2.1

Greater London Authority Area

This plan is reproduced from or based on the OS map by Scotia Gas Networks plc, with the sanction of the controller of HM Stationery Office.Crown Copyright Reserved.

Scotia Gas Networks plc






pipes owned by other GTs or third parties may also be present in this area but are not shown on this plan. Information with regard to such pipes should be obtained from the relevant owners. No warranties are given with regard to the accuracy of the information shown on this plan. Service pipes, valves, siphons, sub-connections etc are not shown but their presence should be anticipated. You should be aware that a small percentage of our pipes/assets may be undergoing review and will temporarily be highlighted in yellow. If your proposed works are close to one of these pipes, you should contact the SGN Plant Protection Team on 08450703497 for advice. No liability of any kind whatsoever is accepted by SGN or its agents, servants or sub-contractors for any error or omission contained herein. Safe digging practices, in accordance with HS (G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that plant location information is provided to all persons (whether direct labour or sub-contractors) working for you on or near gas apparatus. Information included on this plan should not be referred to beyond a period of 28 days from the date of issue.

**INTRANET MAP VERSION 2.1** 

Greater London Authority Area

This plan is reproduced from or based on the OS map by Scotia Gas Networks plc, with the sanction of the controller of HM Stationery Office.Crown Copyright Reserved.

Scotia



Scotia Gas Networks plc

SSSIs

Diameter

Change

GTs


E532870,N178407,TQ 32 78


Cover

Valve ⋈

Some examples of Plant items:

Valve Syphon Syphon






This plan shows the location of those pipes owned by Scotia Gas Networks (SGN) by virtue of being a licensed Gas Transporter (GT). Gas pipes owned by other GTs or third parties may also be present in this area but are not shown on this plan. Information with regard to such pipes should be obtained from the relevant owners. No warranties are given with regard to the accuracy of the information shown on this plan. Service pipes, valves, siphons, sub-connections etc are not shown but their presence should be anticipated. You should be aware that a small percentage of our pipes/assets may be undergoing review and will temporarily be highlighted in yellow. If your proposed works are close to one of these pipes, you should contact the SGN Plant Protection Team on 08450703497 for advice. No liability of any kind whatsoever is accepted by SGN or its agents, servants or sub-contractors for any error or omission contained herein. Safe digging practices, in accordance with HS (G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that plant location information is provided to all persons (whether direct labour or sub-contractors) working for you on or near gas apparatus. Information included on this plan should not be referred to beyond a period of 28 days from the date of issue.


# INTRANET MAP VERSION 2.1

Greater London Authority Area

This plan is reproduced from or based on the OS map by Scotia Gas Networks plc, with the sanction of the controller of HM Stationery Office.Crown Copyright Reserved.

Scotia Gas Networks plc





SCALE 1: 500

USER ID: NS67639

DATE: 04/08/2014

INTERNAL USE ONLY

GRID REFERNCE:
E532846,N178125,TQ 32 78

Some examples of Plant items:
Valve V Depth of Cover

LP MAINS

MP MAINS

IP MAINS

LHP MAINS

LHP MAINS

DEPTH OF COVER

DIAMETER OF CHANGE

Change

LAS


Diameter Change


Material Change

This plan shows the location of those pipes owned by Scotia Gas Networks (SGN) by virtue of being a licensed Gas Transporter (GT). Gas pipes owned by other GTs or third parties may also be present in this area but are not shown on this plan. Information with regard to such pipes should be obtained from the relevant owners. No warranties are given with regard to the accuracy of the information shown on this plan. Service pipes, valves, siphons, sub-connections etc are not shown but their presence should be anticipated. You should be aware that a small percentage of our pipes/assets may be undergoing review and will temporarily be highlighted in yellow. If your proposed works are close to one of these pipes, you should contact the SGN Plant Protection Team on 08450703497 for advice. No liability of any kind whatsoever is accepted by SGN or its agents, servants or sub-contractors for any error or omission contained herein. Safe digging practices, in accordance with HS (G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that plant location information is provided to all persons (whether direct labour or sub-contractors) working for you on or near gas apparatus. Information included on this plan should not be referred to beyond a period of 28 days from the date of issue.

This plan is reproduced from or based on the OS map by Scotia Gas Networks plc, with the sanction of the controller of HM Stationery Office.Crown Copyright Reserved.

Scotia





This plan shows the location of those pipes owned by Scotia Gas Networks (SGN) by virtue of being a licensed Gas Transporter (GT). Gas pipes owned by other GTs or third parties may also be present in this area but are not shown on this plan. Information with regard to such pipes should be obtained from the relevant owners. No warranties are given with regard to the accuracy of the information shown on this plan. Service pipes, valves, siphons, sub-connections etc are not shown but their presence should be anticipated. You should be aware that a small percentage of our pipes/assets may be undergoing review and will temporarily be highlighted in yellow. If your proposed works are close to one of these pipes, you should contact the SGN Plant Protection Team on 08450703497 for advice. No liability of any kind whatsoever is accepted by SGN or its agents, servants or sub-contractors for any error or omission contained herein. Safe digging practices, in accordance with HS (G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that plant location information is provided to all persons (whether direct labour or sub-contractors) working for you on or near gas apparatus. Information included on this plan should not be referred to beyond a period of 28 days from the date of issue.

Greater London Authority Area

This plan is reproduced from or based on the OS map by Scotia Gas Networks plc, with the sanction of the controller of HM Stationery Office.Crown Copyright Reserved.

Scotia Gas Networks plc



SCALE 1: 1250

USER ID: NS67639

DATE: 12/08/2014

INTERNAL USE ONLY

GRID REFERENCE: LAs

E533086,N177992,TQ 33 77

Some examples of Plant items:


Valve Depth of Cover

Syphon Diameter Material Change

This plan shows the location of those pipes owned by Scotia Gas Networks (SGN) by virtue of being a licensed Gas Transporter (GT). Gas pipes owned by other GTs or third parties may also be present in this area but are not shown on this plan. Information with regard to such pipes should be obtained from the relevant owners. No warranties are given with regard to the accuracy of the information shown on this plan. Service pipes, valves, siphons, sub-connections etc are not shown but their presence should be anticipated. You should be aware that a small percentage of our pipes/assets may be undergoing review and will temporarily be highlighted in yellow. If your proposed works are close to one of these pipes, you should contact the SGN Plant Protection Team on 08450703497 for advice. No liability of any kind whatsoever is accepted by SGN or its agents, servants or sub-contractors for any error or omission contained herein. Safe digging practices, in accordance with HS (G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that plant location information is provided to all persons (whether direct labour or sub-contractors) working for you on or near gas apparatus. Information included on this plan should not be referred to beyond a period of 28 days from the date of issue.

This plan is reproduced from or based on the OS map by Scotia Gas Networks plc, with the sanction of the controller of HM Stationery Office. Crown Copyright Reserved.





# Masterplan New Supplies

## Fortune, Wayne

From: mark.benjamin@openreach.co.uk

Sent: 11 April 2014 17:36 To: Fortune, Wayne

Subject: RE: New Connection Enquiry - Aylesbury Estate Regeneration 50600304

## Good Evening Wayne,

I am adding the sites to our database once all the sites have been registered I will send you out a form and request plans .

Kind Regards

### Mark Benjamin

New Site reception

BLP1P7 | Openreach New Sites Office

Telephone: 0800 141 2672

Mobile:

Fax: 01708 752403

Web: WWW.Openreach.co.uk

Openreach installs, services, supports and maintains the wiring, fibres and connections which link tens of millions of homes and businesses in Britain to their Communications Providers' networks.

Think before you print! Consider the environment before printing this e-mail.

#### **British Telecommunications plc**

Registered office: 81 Newgate Street London EC1A 7AJ

Registered in England no. 1800000

This electronic message contains information from British Telecommunications plc which may be privileged and confidential. The information is intended to be for the use of the individual(s) or entity named above. If you are not the intended recipient, be aware that any disclosure, copying, distribution or use of the contents of this information is prohibited. If you have received this electronic message in error, please notify us by telephone or email (to the number or address above) immediately. Activity and use of the British Telecommunications plc email system is monitored to secure its effective operation and for other lawful business purposes. Communications using this system will also be monitored and may be recorded to secure effective operation and for other lawful business purposes.

From: Fortune, Wayne [mailto:Wayne.Fortune@WSPGroup.com]

Sent: 11 April 2014 17:31

To: newsiteromford1 G; Benjamin,MA,Mark,BLP1P7 R

Subject: RE: New Connection Enquiry - Aylesbury Estate Regeneration 50600304

Importance: High

### Good evening Mark,

Looking to follow up on the below correspondence and wanted to confirm how we are going to progress.

Hook forward to your response.

Best regards,

Wayne

From: Fortune, Wayne Sent: 08 April 2014 14:15

To: 'newsitereceptionromford@openreach.co.uk'; Mark Benjamin (mark.benjamin@openreach.co.uk)

Subject: RE: New Connection Enquiry - Aylesbury Estate Regeneration 50600304

Importance: High

Hi Mark,

As per original email we are looking to:

- Detailed connection proposals for Sites 1B/1C and Site 10/Plot 18 to support detailed planning application due August 2014. I have passed on available site layouts, floor plans, etc. for Sites 1B/1C. We do not have any further detailed information for Site 10/Plot 18. We need to know the points of connection to the external network, number of ducts required to be routed within the site, location/size of chambers and any required cabinets (to be located within the public footway) to support the onsite proposals.
- Develop 'high level' proposals for the remainder of the masterplan to support an outline planning application due August 2014. For these sites I have passed on the available masterplan layout, detailed information is not available for these sites hence we are looking for 'high level' proposals e.g. the point of connection to the existing network will be in X and identify if any off-site works are required to support the proposals.

Going forward it may be worthwhile registering each site separately as detailed proposals will be required as each site comes forward for planning, I would suggest the following breakdown which tie up with the attached previously issued drawing – please note the development timescales for interaction between the sites which may impact proposed strategy:

- Site 1B/1C [Plot 1, 2 and 3]
- Plot 18
- Plot 4&5
- Plot 6&7
- Plot 8&9
- Plot 10
- Plot 11
- Plot 12
- Plot 13
- Plot 14&15
- Plot 16&17

Please let me know if you require any further information to progress. As mentioned previously, it would be appreciated if we can set up a meeting between ourselves and Openreach to discuss the requirements through in greater detail.

Many thanks for passing our information on to the network alterations team – is there a point of contact/reference for the project that I can follow up with?

Please call to discuss if need be.


I look forward to your response.

Best regards,

Wayne Fortune MICE MCMI AMIAT Senior Engineer, Power Systems Plus

WSP UK, WSP House, 70 Chancery Lane, London, WC2A 1AF

These are the reference numbers of the other sites please can you send in a site location ,site layout and floors plans for these sites when you start work on them.



L ROD 345 PLOT 5

L ROD 346 PLOT6

**L ROD 347 PLOT 7** 

L ROD 348 PLOT 8

L ROD 349 PLOT 9

L ROD 350 PLOT 10

LROD 351 PLOT 11

L ROD 352 PLOT 12

L ROD 353 PLOT13

L ROD 354 PLOT 14

L ROD 355 PLOT 15

L ROD 356 PLOT 16

L ROD 357 PLOT 17

L ROD 358 PLOT 18

## Legena

### CAUTION\_AREA

BT.CAUTION\_AREA

#### **EQUIPMENT**

TABED FIBRE, TCODE

OPPER, CABINET

476R COPPER, DP

### **DUCT**

AERIAL

TUNNEL DUCT

### PROPOSED

-AC - AERIAL

--- DUCT

### **STRUCTURE**

□ CABINET SHELL

× SPLIT COUPLING

O POLE

KIOSKS

MANHOLE

**■** JOINTBOX

CHANGE OF STATE

DUCT TEE

#### PROPOSED


MANHOLE

☑ JOINTBOX

DUCT TEE

Other proposed plant is shown using

BT symbols not listed above may be disregarded.



Reproduced by permission of Ordnance Survey on behalf of HMSO. © Crown copyright and database right 2013 . All rights reserved. Ordnance Survey Licence number 100028040

#### IMPORTANT WARNING:

Information regarding the location of BT apparatus is given for your assistance and is intend for general guidance only. No guarante is given of its accuracy, it should not be relied upon in the event of excavations or other works being made near to BT apparatus, which may exist at various depiths and may deviate from the marked route.

Exisiting BT plant may not be recorded.

FOR FREE ON-SITE LOCATION & MARKING SERVICE CALL THE EXCHANGE OPERATOR AND ASK FOR :-

FREEPHONE 0800 9173993 FAX 0208 3284050 NATIONAL NEWSITES 0800 616866





#### PLANT INFORMATION REPLY

<Double-Click to add Text>

<Double-Click to add Text>

openreach

# Legena

# CAUTION\_AREA

BT.CAUTION\_AREA

#### **EQUIPMENT**

TABED FIBRE, TCODE

COPPER, CABINET

476R COPPER, DP

#### DUCT

AERIAL

TUNNEL

--- DUCT

### PROPOSED

--- AERIAL

STRUCTURE

#### YCODE

CABINET SHELL

× SPLIT COUPLING

O POLE

**®** KIOSKS

MANHOLE

JOINTBOX

CHANGE OF STATE

DUCT TEE

#### PROPOSED


■ MANHOLE

JOINTBOX

DUCT TEE

Other proposed plant is shown using dashed lines.

BT symbols not listed above may be disregarded.



Reproduced by permission of Ordnance Survey on behalf of HMSO. © Crown copyright and database right 2013. All rights reserved, Ordnance Survey Licence number 100028040


IMPORTANT WARNING

Information regarding the location of BT apparatus is given for your assistance and is intend for general guidance only. No guarantee is given of its accuracy, it should not be relied upon in the event of excavations or other works being made near to BT apparatus, which may exist at various depths and may deviate from the marked route.

Exisiting BT plant may not be recorded. Information valid at time of preparation.

FOR FREE ON-SITE LOCATION & MARKING SERVICE CALL THE EXCHANGE OPERATOR AND ASK FOR:-

FREEPHONE 0800 9173993 FAX 0208 3284050 NATIONAL NEWSITES 0800 616866





### PLANT INFORMATION REPLY

<Double-Click to add Text>

<Double-Click to add Text>

openreach

# Legend

### CAUTION\_AREA

BT.CAUTION\_AREA

#### **EQUIPMENT**

TABED FIBRE, TCODE

COPPER, CABINET

476R COPPER, DP

### DUCT

AC AERIAL

TUNNEL

--- DUCT

#### PROPOSED

-A'C - AERIAL

### **STRUCTURE**

CABINET SHELL

× SPLIT COUPLING

O POLE

KIOSKS

MANHOLE

JOINTBOX

/ CHANGE OF STATE

DUCT TEE

#### PROPOSED


MANHOLE

JOINTBOX

DUCT TEE

Other proposed plant is shown using dashed lines.

BT symbols not listed above may be disregarded.



Reproduced by permission of Ordnance Survey on behalf of HMSO. © Crown copyright and database right 2013. All rights reserved. Ordnance Survey Licence number 100028040


IMPORTANT WARNING

Information regarding the location of BT apparatus is given for your assistance and is intend for general guidance only. No guarantee is given of its accuracy, it should not be relied upon in the event of excavations or other works being made near to BT apparatus, which may exist at various depths and may deviate from the marked route.

Exisiting BT plant may not be recorded. Information valid at time of preparation.

FOR FREE ON-SITE LOCATION & MARKING SERVICE CALL THE EXCHANGE OPERATOR AND ASK FOR:-

FREEPHONE 0800 9173993 FAX 0208 3284050 NATIONAL NEWSITES 0800 616866





#### PLANT INFORMATION REPLY

<Double-Click to add Text>

<Double-Click to add Text>



# Legena

#### CAUTION AREA

BT.CAUTION\_AREA

#### EQUIPMENT

TABED FIBRE, TCODE

476R COPPER, DP

#### DUCT

AERIAL

TUNNEL — DUCT

#### PROPOSED

-AC - AERIAL

--- DUCT

### STRUCTURE

YCODE

CABINET SHELL

× SPLIT COUPLING

O POLE

KIOSKS

MANHOLE

JOINTBOX

CHANGE OF STATE

DUCT TEE

#### PROPOSED


MANHOLE

☑ JOINTBOX

DUCT TEE

Other proposed plant is shown using dashed lines.

BT symbols not listed above may be disregarded.



Reproduced by permission of Ordnance Survey on behalf of HMSO. © Crown copyright and database right 2013. All rights reserved. Ordnance Survey Licence number: 100028040

IMPORTANT WARNING:

Information regarding the location of BT apparatus is given for your assistance and is intend for general guidance only. No guarantee is given of its accuracy. It should not be relied upon in the event of excavations or other works being made near to BT apparatus, which may exist at various depths and may deviate from the marked route. Exisiting BT plant may not be recorded

FOR FREE ON-SITE LOCATION & MARKING SERVICE CALL THE EXCHANGE OPERATOR AND ASK FOR :-

FREEPHONE 0800 9173993 FAX 0208 3284050 NATIONAL NEWSITES 0800 616866



### PLANT INFORMATION REPLY

<Double-Click to add Text>

<Double-Click to add Text>

#### SITE 8 DIVERSION ROUTES Legena JOINT BOX510 EM S212 CAUTION AREA BT.CAUTION\_AREA JOINT BOXJOINT BOXJOINT BOX **EQUIPMENT** JOINT BOX JOINT BOX TABED FIBRE, TOODE JOINT BO JOINT BOX COPPER, CABINET (915)E JOINT BOX 476R COPPER, DP DUCT AERIAL Sub Sta TUNNEL - DUCT 197/E PROPOSED **JBF 106** -AC - AERIAL 1688 I --- DUCT Sub Sta JOINT BO STRUCTURE YCODE □ CABINET SHELL Sacred Hear SPLIT COUPLING ŎINT BOX **JBF 104B** YSZOYLGNU O POLE KIOSKS MANHOLE Chaplin GOINT BO T16 JOINTBOX CHANGE OF STATE YOINT BOX DUCT TEE **√**Γ BOX PROPOSED 4102/1 (90)I\\* MANHOLE JOINT BO 694 ROJOINT BOX JOINTBOX DUCT TEE JOINT BOX Other proposed plant is shown using dashed lines. BT symbols not listed above may be disregarded. Reproduced by permission of Ordnance Survey on behalf of HMSO. © Crown copyright and database right 2013 . All rights reserved. Ordnance Survey Licence number 10002804 Exisiting BT plant may not be recorded IMPORTANT WARNING: PLANT INFORMATION REPLY Information regarding the location of BT apparatus is Information valid at time of preparation given for your assistance and is intend for general <Double-Click to add Text> guidance only. No guarantee is given of its accuracy. It should not be relied upon in the event of excavations FOR FREE ON-SITE LOCATION & MARKING SERVICE openreach PRODIED BT or other works being made near to BT apparatus, which may exist at various depths and may deviate from the marked route <Double-Click to add Text> FREEPHONE 0800 9173993 NATIONAL NEWSITES 0800 616866



WSP HOUSE 70 CHANCERY LANE LONDON WC2A 1AF BT OPENREACH REPAYMENTS PROJECTS POST POINT 300 CLERKENWELL TE 35 IRONMONGER ROW LONDON EC1V 3RJ

F. A. O. Wayne Fortune

Our Ref: 213112 Your Ref: SITE 9 Telephone: 0207 749 8701 Facsimile: 01908 860174

Date: 24 July 2014

Dear Sir.

# RE: AYLESBURY ESTATE SITE 9 THURLOW STREET LONDON

Thank you for your letter and drawings dated 19th February 2014, concerning the above scheme.

I am returning copy of BT ordnance drawings showing approximate positions of BT apparatus.

BT apparatus may not be affected by your proposed works if the Manholes marked in red are left in-situ as per our earlier discussions.

Please contact our Plant Protection Officer by dialling 0800 917 3993 and asking for Dial Before You Dig to locate our existing apparatus well in advance of your start date. This will provide you with free on site advice and confirm the location of our apparatus.

If you wish to discuss your proposals further, please do not hesitate to contact me.

Yours faithfully

**B** Chohan

**Projects Engineer** 



WSP HOUSE 70 CHANCERY LANE LONDON WC2A 1AF BT OPENREACH REPAYMENTS PROJECTS POST POINT 300 CLERKENWELL TE 35 IRONMONGER ROW LONDON EC1V 3RJ

F. A. O. Wayne Fortune

Our Ref: 213855

Your Ref: SITE 11 & 12

Telephone: 0207 749 8701 Facsimile: 01908 860174

Date: 02 August 2014

Dear Sir.

### RE: AYLESBURY ESTATE SITE 11 & 12 THURLOW STREET LONDON

Thank you for your letter and drawings dated 19<sup>th</sup> February 2014, concerning the above scheme.

I am returning copy of BT ordnance drawings showing approximate positions of BT apparatus.

BT apparatus may not be affected by your proposed works..

Please contact our Plant Protection Officer by dialling 0800 917 3993 and asking for Dial Before You Dig to locate our existing apparatus well in advance of your start date. This will provide you with free on site advice and confirm the location of our apparatus.

If you wish to discuss your proposals further, please do not hesitate to contact me.

Yours faithfully

**B** Chohan

**Projects Engineer** 

### Legena

### CAUTION AREA

BT.CAUTION\_AREA

#### **EQUIPMENT**

TABED FIBRE, TCODE

476R COPPER, DP

### DUCT

A/C AERIAL

TUNNEL

- DUCT

#### PROPOSED

-AC - AERIAL

--- DUCT

# **STRUCTURE**

YCODE

☐ CABINET SHELL

K SPLIT COUPLING

O POLE

**®** KIOSKS

MANHOLE

JOINTBOX

/ CHANGE OF STATE

DUCT TEE

#### PROPOSED


MANHOLE

■ JOINTBOX

DUCT TEE

Other proposed plant is shown using dashed lines.

BT symbols not listed above may be disregarded.



eproduced by permission of Ordnance Survey on behalf of HMSO. © Crown copyright and database right 2013. All rights reserved. Ordnance Survey Licence number 100028040

#### IMPORTANT WARNING

Information regarding the location of BT apparatus is given for your assistance and is intend for general guidance only. No guarantee is given of its accuracy, it should not be relied upon in the event of excavations or other works being made near to BT apparatus, which may exist at various depths and may deviate from the marked rout Exisiting BT plant may not be recorded. Information valid at time of preparation.

FOR FREE ON-SITE LOCATION & MARKING SERVICE CALL THE EXCHANGE OPERATOR AND ASK FOR :-

FREEPHONE 0800 9173993 FAX 0208 3284050 NATIONAL NEWSITES 0800 616866





# PLANT INFORMATION REPLY

<Double-Click to add Text>

<Double-Click to add Text>

openreach

## Legena

# CAUTION\_AREA

BT.CAUTION\_AREA

#### **EQUIPMENT**

TABED FIBRE, TCODE

COPPER, CABINET

476R COPPER, DP

#### DUCT

AERIAL

TUNNEL

— DUCT

#### PROPOSED

-AC - AERIAL

--- DUCT

### **STRUCTURE**

☐ CABINET SHELL

× SPLIT COUPLING

O POLE

KIOSKS

MANHOLE

JOINTBOX

/ CHANGE OF STATE

DUCT TEE


#### PROPOSED

■ MANHOLE

DUCT TEE

Other proposed plant is shown using

BT symbols not listed above may be disregarded.



Reproduced by permission of Ordnance Survey on behalf of HMSO. © Crown copyright and database right 2013. All rights reserved. Ordnance Survey Licence number 100028040

Information regarding the location of BT apparatus is given for your assistance and is intend for general guidance only. No guarantee is given of its accuracy. It should not be relied upon in the event of excavations or other works being made near to BT apparatus, which may exist at various depths and may deviate from the marked route

IMPORTANT WARNING:

Exisiting BT plant may not be recorded Information valid at time of preparation

FOR FREE ON-SITE LOCATION & MARKING SERVICE CALL THE EXCHANGE OPERATOR AND ASK FOR:-

FREEPHONE 0800 9173993 FAX 0208 3284050 NATIONAL NEWSITES 0800 616866



#### PLANT INFORMATION REPLY

<Double-Click to add Text>

<Double-Click to add Text>

openreach



WSP HOUSE 70 CHANCERY LANE LONDON WC2A 1AF BT OPENREACH REPAYMENTS PROJECTS POST POINT 300 CLERKENWELL TE 35 IRONMONGER ROW LONDON EC1V 3RJ

F. A. O. Wayne Fortune

Our Ref: 213854

Your Ref: SITE 3A & 3B

Telephone: 0207 749 8701 Facsimile: 01908 860174

Date: 02 August 2014

Dear Sir.

# RE: AYLESBURY ESTATE SITE 3A & 3B THURLOW STREET ALBANY ROAD LONDON

Thank you for your letter and drawings dated 19th February 2014, concerning the above scheme.

I am returning copy of BT ordnance drawings showing approximate positions of BT apparatus.

BT apparatus may not be affected by your proposed works.

Please contact our Plant Protection Officer by dialling 0800 917 3993 and asking for Dial Before You Dig to locate our existing apparatus well in advance of your start date. This will provide you with free on site advice and confirm the location of our apparatus.

If you wish to discuss your proposals further, please do not hesitate to contact me.

Yours faithfully

**B** Chohan

**Projects Engineer** 

### Legena

### CAUTION\_AREA

BT.CAUTION\_AREA

#### **EQUIPMENT**

TABED FIBRE, TCODE

476R COPPER, DP

#### DUCT

AERIAL

TUNNEL DUCT

#### PROPOSED

-AC - AERIAL

--- DUCT

### **STRUCTURE**

YCODE

CABINET SHELL

× SPLIT COUPLING

O POLE

KIOSKS

MANHOLE

JOINTBOX

/ CHANGE OF STATE

DUCT TEE

#### PROPOSED


■ MANHOLE

■ JOINTBOX

DUCT TEE

Other proposed plant is shown using dashed lines.

BT symbols not listed above may be disregarded.



Reproduced by permission of Ordnance Survey on behalf of HMSO, © Crown copyright and database right 2013. All rights reserved. Ordnance Survey Licence number 100028040

IMPORTANT WARNING

Information regarding the location of BT apparatus is given for your assistance and is intend for general guidance only. No guarantee is given of its accuracy, it should not be relied upon in the event of excavations or other works being made near to BT apparatus, which may exist at various depths and may deviate from the marked route.

Exisiting BT plant may not be recorded. Information valid at time of preparation.

FOR FREE ON-SITE LOCATION & MARKING SERVICE CALL THE EXCHANGE OPERATOR AND ASK FOR :-

FREEPHONE 0800 9173993 FAX 0208 3284050 NATIONAL NEWSITES 0800 616866 PROPOSED BT BUCT ROUTE



PLANT INFORMATION REPLY			
<double-click add="" text="" to=""></double-click>	openreach		
<double-click add="" text="" to=""></double-click>	a BT Group business BT		

### Masterplan New Supplies

## Fortune, Wayne

From: Rosi, Paul <paul.rosi@virginmedia.co.uk>

Sent: 07 March 2014 13:22
To: Fortune, Wayne
Cc: Sharp, Fidel

Subject: FW: New Connection Enquiry - Aylesbury Estate Regeneration 50600304

## Hi Wayne

As discussed, it shouldn't be a problem for us to add around 900 homes to our network in this area within our new build budget however I can't confirm until we receive detailed plans

Please send the following over as soon as you can so we can confirm;

Masterplan
Scaled site plan
Elevation plans
Number of floors and number of units per floor

#### **Thanks**

Paul Rosi | National New Build Officer - London & South East Virgin Media | Comms House, 5 Factory Lane, Croydon, Surrey, CR9 3RA M 07985 807162 | D 0208 251 6848 | F 0208 251 6748 | E paul.rosi@virginmedia.co.uk Visit www.virginmedia.com for more information and more fun.

Please consider the environment before printing this e-mail

From: Fortune, Wayne [mailto:Wayne.Fortune@WSPGroup.com]

Sent: 03 March 2014 10:31

To: >TW Diversionary; >New Build

Subject: RE: New Connection Enquiry - Aylesbury Estate Regeneration 50600304

Dear Sirs.

I submitted the below enquiry on 19<sup>th</sup> February 2014 for the Aylesbury Estate Regeneration project.

Please confirm that our enquiry has been received and is being progressed.

Due to the size and complexity of the project it would be appreciated if we can set up an early meeting/workshop with Virgin Media to discuss requirements for the project.

Hook forward to your response.

Yours sincerely,

Wayne Fortune MICE MCMI AMIAT Senior Engineer, Power Systems Plus

WSP UK, WSP House, 70 Chancery Lane, London, WC2A 1AF

Tel: +44 (0)20 7314 5872 Mob: +44 (0)7887 059 695

#### Website: www.wspgroup.co.uk

#### We are WSP

British Construction Industry (BCI) Major Project of the Year Award winner for The Shard 2013

WSP is one of the world's leading professional services firms, working with governments, businesses, architects and planners and providing integrated solutions across many disciplines. The firm provides services to transform the built environment and restore the natural environment. It has approximately 15,000 employees, based in more than 300 offices, across 35 countries, on every continent.

#### Confidential

This message, including any document or file attached, is intended only for the addressee and may contain privileged and/or confidential information. Any other person is strictly prohibited from reading, using, disclosing or copying this message. If you have received this message in error, please notify the sender and delete the message.

WSP UK Limited Registered Office: WSP House, 70 Chancery Lane, London, WC2A 1AF Registered Number 01383511 England



If possible, please consider saving paper by not printing your e-mail.

From: Fortune, Wayne

Sent: 19 February 2014 17:52

To: Diversionary@virginmedia.co.uk; new.developments@virginmedia.co.uk

Cc: Edwards, Alastair

Subject: New Connection Enquiry - Aylesbury Estate Regeneration 50600304

Dear Sirs.

Location of Works: Aylesbury Estate Regeneration

O.S. Grid Ref: TO 32708 77782 Street Name: Albany Road Programme: 2015 - 2032

Description of Works: redevelopment of the Aylesbury Estate

WSP are working on behalf of Notting Hill Housing, which has been appointed by the London Borough of Southwark as its preferred partner for the phased demolition and redevelopment of the Aylesbury Estate. Subject to the finalisation of contract negotiations, it is the intention of Notting Hill Housing to seek planning approval towards the end of 2014 – in detail for the first phase of the redevelopment, and outline for the remainder of the redevelopment.

Due the size of the proposed development we are seeking to engage Virgin Media at an early stage to understand if there is network capacity to support the site proposals and obtain indicative costs for any works required to provide connectivity to the site.

It is anticipated that Sites 1B/1C and Site10/Plot 18 will commence demolition/construction in 2015 and the anticipated programme for the remainder of the sites is to 2032.

It would be appreciated if we can set up an early meeting/workshop to discuss the connection and diversion proposals for the masterplan.

## Existing Residential Units (all assumed to be flats)

Studio	45
1 Bedroom	507
2 Bedroom	896
3 Bedroom	828
4 Bedroom	283
5 Bedroom	88
Total	2647

### **Proposed Units**

1 bed flat	1003	Other use areas:
2 bed flat	1020	2,000m <sup>2</sup> Community Space
3 bed flat	336	500m <sup>2</sup> Fast Food Outlet 1,000m <sup>2</sup> Minor Retail Units
2 bed maisonette	170	1,500m <sup>2</sup> Medical Centre
3 bed maisonette	364	2,500m <sup>2</sup> Office Space
4 bed maisonette	60	·
4 bed house	363	
5 bed house	222	
Total	3538	Use areas assumed based on available information.

Detailed development of the new connection proposals will be required for Sites 1B/1C and Site 10/Plot 18 to support detailed planning application due August 2014. High level development of the new proposals will be required for the remaining sites to support an outline planning application due August 2014. Find attached SK-PSP-003 COMMS GROWTH which provides the indicated phased growth for the masterplan and SK-PSP-013 VM DIVERSIONS which highlights the required disconnections, diversions, etc. to accommodate the masterplan proposals.

Please note that the accommodation mix/areas, etc. are subject to change during masterplanning.

Can you please provide an indication of the timescales for providing a response to our enquiry and please highlight any further information required to progress.

Please do not hesitate to get in touch to discuss.

Yours faithfully,

Wayne Fortune MICE MCMI AMIAT Senior Engineer, Power Systems Plus

WSP UK, WSP House, 70 Chancery Lane, London, WC2A 1AF

Tel: +44 (0)20 7314 5872 Mob: +44 (0)7887 059 695

Website: www.wspgroup.co.uk

We are WSP

British Construction Industry (BCI) Major Project of the Year Award winner for The Shard 2013

WSP is one of the world's leading professional services firms, working with governments, businesses, architects and planners and providing integrated solutions across many disciplines. The firm provides services to transform the built environment and restore the natural environment. It has approximately 15,000 employees, based in more than 300 offices, across 35 countries, on every continent.

#### Confidential


This message, including any document or file attached, is intended only for the addressee and may contain privileged and/or confidential information. Any other person is strictly prohibited from reading, using, disclosing or copying this message. If you have received this message in error, please notify the sender and delete the message.


WSP UK Limited Registered Office: WSP House, 70 Chancery Lane, London, WC2A 1AF Registered Number 01383511 England





If possible, please consider saving paper by not printing your e-mail.


Save Paper - Do you really need to print this e-mail?





























Your ref

Our ref NRSWA/3.03/001700

Date 26-08-2014.

6

Smale House 114 Great Suffolk Street London SE1 0SL

C3requests@vodafone.com

Name
Wayne Fortune
WSP UK,
7 Lochside View,
Edinburgh Park,
Edinburgh,
EH12 9DH

#### **Budget Estimate Diversion/Protection of Vodafone Apparatus**

Dear Sirs,

#### New Roads and Street Works Act 1991

#### Proposed Works at: Aylesbury Estate, Merrow Street and Dawes Street.

Please find detailed below, a budget estimate for carrying out the necessary diversion/protection to Vodafone Limited's apparatus due to your proposed work. The estimated cost for these works is £9,814 plus VAT. Please be aware we reserve the right to amend this estimate dependent upon the actual costs of the works.

This estimate is based upon the current information provided and allows

Lowering of approximately 30m of the existing Vodafone apparatus over the area of your proposed works. This has been made on the assumption that access to existing apparatus and the space around our existing ducts is available. We would recommend that prior to requesting a C4 estimate, you undertake trial holes, and share them with all utilities, to help determine whether a slew/lower operation would be possible. If slew/lowering is not achievable, C&W requirements would have to be re-assessed and a full cable divert would have to be considered with the associated increase in costs and increased timescales.

Under the CDM regulations, please could you provide us with any risks or hazards that may be associated with these works.

The approximate lead-in time the implementation of civils only works is 6 working weeks from receipt of the Order/payment. If a full cable diversion is required then this lead-in time will extend to approximately 20 weeks.

Please note that Vodafone operate a full network freeze, during which no works can be carried out on our network, between 1<sup>st</sup> December and the first week of January every year, which may impact on the timescales for your works.

If you wish to obtain a C4 detailed estimate, the cost of providing this is £2500 plus VAT.

This letter is based upon the current information provided in respect of your proposed works and relates to Vodafone Limited's underground fibre optic network only, which includes all former companies; Cable & Wireless UK, Energis Communications Limited, Thus PLC and Your Communications Limited's networks.

**Vodafone Limited** 

The Connection, Newbury, Berkshire, RG14 2FN, United Kingdom Phone +44 (0)1635 33251 Fax +44 (0)1635 682729



All work will be carried out by a Vodafone approved contractor on receipt of your unconditional Order and correct advanced deposit. This should be made payable to "Vodafone Limited" for the attention of Rob Baker at Vodafone Diversionary Works Team, Smale House, Floor 2E, 114 Great Suffolk Street, London SE1 0SL.

Please quote the following reference in all correspondence/instructions to proceed: NRSWA/3.03/001700.

This estimate will remain valid for a period of three months from the date of this letter and all works resulting from this estimate shall be subject to the terms and conditions of Vodafone and/or where applicable the terms and conditions dictated by the New Roads & Street Works Act 1991 and associated codes of practice.

Please note that under the Diversionary Works Code of Practice, Appendix C and the associated Regulations that apply, Promoters are only entitled to one desktop costing per any given scheme. Any change in scope or a subsequent request for a revised costing on the same scheme is then deemed chargeable and will only be reviewed under the C4 Process.

Yours faithfully

Diversionary Works Team Vodafone



#### **WSP UK**

FAO Mr Wayne Fortune WSP House 70 Chancery Lane London WC2A 1AF Thames Water Utilities Ltd. Developer Services

Your ref

Our ref 50023275

Name Richard Allen

Phone 0845 850 2777

E-Mail developer.services@thameswater.co.uk

4th Sept 2014

Dear Mr Fortune

# Clean Water Budget Estimate for Diversions & New Supplies for Aylesbury Estate Regeneration, Albany Rd, London, SE17

Thank you for your request for budget estimates for diversions and new supplies for the Aylesbury Estate Regeneration project.

I can confirm that Thames Water are in the process of preparing budgets for Phases 2,3 and 4 and Site 10/Plot 18 of the project and will provide the requested information when available.

Yours sincerely

Richard Allen

Thames Water Developer Services 0845 8502777

Thames Water Utilities Ltd

Developer Services 3<sup>rd</sup> Floor West Clear Water Court Vastern Road Reading Berkshire RG1 8DB

T 0845 850 2777

I www.thameswater.co.uk

Registered in England and Wales No. 2366661, Registered office Clearwater Court, Vastern Road, Reading, Berks. RG1 8DB

## Fortune, Wayne

From: Karl Tuchscherer < karl.tuchscherer@thameswater.co.uk>

Sent: 06 August 2014 14:39 To: Fortune, Wayne

Subject: RE: IRef:1011778601 Aylesbury Estate Regeneration Walworth SE17 2UQ

Wayne,

I agree with the below.

Regards

Karl.

From: Fortune, Wayne [mailto:Wayne.Fortune@WSPGroup.com]

Sent: 06 August 2014 14:38

To: Karl Tuchscherer

Cc: Dyason, James; Edwards, Alastair; Dagnall, Mike

Subject: RE: IRef:1011778601 Aylesbury Estate Regeneration Walworth SE17 2UQ

Karl,

Thanks for wording/update in terms of the on-going exercise.

From our discussion and for my own clarification, current stance is;

- Thames Water confirm network modelling is required and underway and development should not commence until this exercise is complete.
- Initial feedback is that there is insufficient capacity within the existing network to accommodate the masterplan based on submitted potable water loads.
- On completion of the network studies, Thames Water will look at solutions e.g. required offsite reinforcement, rezoning supplies, alternative pressure systems, etc. to potentially avoid laying new trunk mains within the development
- On-site options to reduce magnitude of reinforcement may include on-site storage, incorporate of low flow/reduced water using appliances, etc.

Best regards,

## Wayne

 $From: Karl\ Tuch scherer\ [\underline{mailto: karl.tuch scherer@thameswater.co.uk}]$ 

Sent: 06 August 2014 14:09

To: Fortune, Wayne

Subject: RE: IRef:1011778601 Aylesbury Estate Regeneration Walworth SE17 2UQ

Wayne,

The existing water supply infrastructure has insufficient capacity to meet the additional demands for the proposed development. Thames Water therefore recommend the following condition be imposed: Development should not be commenced until: Impact studies of the existing water supply infrastructure have been submitted to, and approved in writing by, the local planning authority (in consultation with Thames Water). The studies should determine the magnitude of any new additional capacity required in the system and a suitable connection point. Reason: To ensure that the water supply infrastructure has sufficient capacity to cope with the/this additional

demand. These studies are currently being undertaken with a completion date of the 5/9/2014, once completed solution will be available to supply the redevelopment of the Estate.

Thames Water recommend the following informative be attached to this planning permission. Thames Water will aim to provide customers with a minimum pressure of 10m head (approx 1 bar) and a flow rate of 9 litres/minute at the point where it leaves Thames Waters pipes. The developer should take account of this minimum pressure in the design of the proposed development.

Regards

Karl.

From: Fortune, Wayne [mailto:Wayne.Fortune@WSPGroup.com]

Sent: 05 August 2014 10:23 To: Developer Services Cc: Karl Tuchscherer

Subject: IRef:1011778601 Aylesbury Estate Regeneration Walworth SE17 2UQ

Importance: High

**FAO Karl Tuchscherer** 

Karl,

I know we are not due to complete the network modelling for the masterplan site until 5/9/2014, however we are in the process of preparing the planning submission and EIA chapters that go with it.

As previously discussed, we are looking for Thames Water to provide some text which can sit within our EIA chapters to satisfy the planning conditions with respect to clean water.

It would also be good if you are able to provide us with any early findings from the network modelling which may be of use in this instance.

Can you please arrange for this information to be provided to myself by Wednesday 6/8/2014.

Please call to discuss if need be.

Best regards,

Wayne Fortune MICE MCMI AMIAT Senior Engineer, Power Systems Plus

WSP UK, 7 Lochside View, Edinburgh Park, Edinburgh, EH12 9DH

Tel: +44 (0)131 344 2374 Mob: +44 (0)7887 059 695

Website: www.wspgroup.co.uk

We are WSP

British Construction Industry (BCI) Major Project of the Year Award winner for The Shard 2013


WSP is one of the world's leading professional services firms, working with governments, businesses, architects and planners and providing integrated solutions across many disciplines. The firm provides services to transform the built environment and restore the natural environment. It has approximately 15,000 employees, based in more than 300 offices, across 35 countries, on every continent.


#### Confidential


This message, including any document or file attached, is intended only for the addressee and may contain privileged and/or confidential information. Any other person is strictly prohibited from reading, using, disclosing or copying this message. If you have received this message in error, please notify the sender and delete the message. Thank you.

# Appendix 3

Project number: 50600304 Dated: 15/08/2014 Revised: 05/09/2014







401567158 C

Our Ref: 818933

Your Ref: None Given



SGN Connections Limited St. Lawrence House Station Approach Horley Surrey RH6 9HJ

Tel: 0800 912 1700

Mr Wayne Fortune WSP UK 7 Lochside View Edinburgh Park Edinburgh EH12 9DH

01/09/2014

Dear Mr Fortune,

## RE: New connections at Aylesbury Estate Regeneration Site 1B/1C, Albany Road, London, SE5 0AW

Further to your request dated 30<sup>th</sup> July 2014 regarding the new connections at the above site, please find a budget indication quote detailed below.

**Works to be carried out:** SGN Connections to connect to the existing 75mm PE LP Main within Westmoreland Road & the Proposed (Diversion Main)180mm PE LP to be installed within Portland Street and install appropriately sized gas mains/service infrastructure to suitable location(s). SGN Connections to provide all excavation and reinstatement upto the customers site boundary. 47 x Semi-concealed Meter Boxes & 2 x GC4 GRP Kiosks to be provided and fitted by SGN. Customer to provided concrete bases for kiosks.

#### Your Budget Indication is: £ 45,400.00 (inc.VAT)

Please note that this figure is a budget indication only and does not represent an offer to carry out the work. This budget cost is based on the information we have been provided with by you.

Upon acceptance of a firm quotation, Southern Gas Networks will need to run further analysis to ensure that the existing gas infrastructure can manage your new gas loads (Security of Supply Check). If the existing infrastructure requires reinforcing to accommodate your loads, then this will incur time delays to the installation of your gas supplies. Reinforcement costs will be met by Southern Gas Networks and we will contact you where required.

It is assumed that no easements or third party permissions are required to carry out all works.

Please note that this budget indication does not take into account for any existing Southern Gas Networks infrastructure that may require diverting. Details of these can be obtained from Southern Gas Networks Diversions/Isolations – 0845 070 3497.

24 hour gas escape number 0800 111 999\*
\*Calls will be recorded and may be monitored

SGN Connections is part of Scotia Gas Networks
Registered in England No. 05618886
Registered Office: St. Lawrence House, Station Approach, Horley, Surrey, RH 9HJ
www.sgn.co.uk

----

If you have any further queries relating to this budget indication, please feel free to contact me on the telephone number at the top of this letter.


Yours sincerely, Anton Siwicki Design Assistant


24 hour gas escape number 0800 111 999\*
\*Calls will be recorded and may be monitored

SGN Connections is part of Scotia Gas Networks
Registered in England No. 05618886
Registered Office: St. Lawrence House, Station Approach, Horley, Surrey, RH
9HJ
www.sgn.co.uk

.....









shown but their presence should be anticipated. You should be aware that a small percentage of our pipes/assets may be undergoing review and will temporarily be highlighted in yellow. If your proposed works are close to one of these pipes, you should contact the SGN Plant Protection Team on 08450703497 for advice. No liability of any kind whatsoever is accepted by SGN or its agents, servants or sub-contractors for any error or omission contained herein. Safe digging practices, in accordance with HS (G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that plant location information is provided to all persons (whether direct labour or sub-contractors) working for you on or near gas apparatus. Information included on this plan should not be referred to beyond a period of 28 days from the date of issue.

Greater London Authority Area

This plan is reproduced from or based on the OS map by Scotia Gas Networks plc, with the sanction of the controller of HM Stationery Office. Crown Copyright Reserved.

Scotia Gas Networks plc






This plan shows the location of those pipes owned by Scotia Gas Networks (SGN) by virtue of being a licensed Gas Transporter (GT). Gas pipes owned by other GTs or third parties may also be present in this area but are not shown on this plan. Information with regard to such pipes should be obtained from the relevant owners. No warranties are given with regard to the accuracy of the information shown on this plan. Service pipes, valves, siphons, sub-connections etc are not shown but their presence should be anticipated. You should be aware that a small percentage of our pipes/assets may be undergoing review and will temporarily be highlighted in yellow. If your proposed works are close to one of these pipes, you should contact the SGN Plant Protection Team on 08450703497 for advice. No liability of any kind whatsoever is accepted by SGN or its agents, servants or sub-contractors for any error or omission contained herein. Safe digging practices, in accordance with HS (G)47, must be used to verify and establish the actual position of mains, pipes, services and other apparatus on site before any mechanical plant is used. It is your responsibility to ensure that plant location information is provided to all persons (whether direct labour or sub-contractors) working for you on or near gas apparatus. Information included on this plan should not be referred to beyond a period of 28 days from the date of issue.

## INTRANET MAP VERSION 2.1

Greater London Authority Area

This plan is reproduced from or based on the OS map by Scotia Gas Networks plc, with the sanction of the controller of HM Stationery Office.Crown Copyright Reserved.

Scotia Gas Networks plc



## Fortune, Wayne

From: martin.jenns@openreach.co.uk

Sent: 07 August 2014 09:33

To: Fortune, Wayne

Cc: nicola.portervaughan@openreach.co.uk

Subject: FTTP

Attachments: 140725 Site 1B\_C Aylesbury Estate\_Fibre Forecast Request Form V12 December

13.pdf; PROP 2 L ROD 341.pdf

Wayne

Thanks for your discussion this morning,

As discussed please send me the site next year much nearer the start date, preferably two to three months in advance of site start date. We can then log you onto the pilot programme. By then you will have more accurate dates for us to work to. The dates you have provided are too vague.

Please would you be so kind as to include a red line drawing of the whole site from phase one to the final phase in 2020, so we can get a feel of the potential pipeline.

Martin Jenns

Fibre To The Premises Co-ordinator London & SE

Events & Exhibitions Co-ordinator London & SE

Office Number 01452 770400

Mobile Number 07802 192417 (Always try my landline number first)

(Group email for Events) LHC Events G

Openreach installs, services, supports and maintains the wiring, fibres and connections which link tens of millions of homes and businesses in Britain to their Communications Providers' networks.

Think before you print! Consider the environment before printing this e-mail.

This email contains BT information, which may be privileged or confidential. It's meant only for the individual(s) or entity named above. If you're not the intended recipient, note that disclosing, copying, distributing or using this information is prohibited. If you've received this email in error, please let me know immediately on the email address above. Thank you.


We monitor our email system, and may record your emails.


British Telecommunications plc

Registered office: 81 Newgate Street London EC1A 7AJ


Registered in England no. 1800000
















Information shown on the enclosed plan is for indication only. No warranty is made to its accuracy. This plan must not be relied upon in the event of excavation or other works carried out in the vicinity of Virgin Media plant. No liability of any kind whatsoever is accepted by Virgin Media, its servants or agents for any error or omission in respect of information contained on this plan. The actual position of the underground services must be verified and established on site before any mechanical plant is used.

































OPERATION No: GRID REF OPERATION No: GRID REF OPERATION No: GRID REF OPERATION No: GRID REF  AS LAID SIGN OFF ROUTE OF NEW MAIN & APPARATUS AS INDICATED DEPTH OF COMER OF NEW MAIN DET	OPERATION NO: GRID REF OPERATION NO: GRID REF OPERATION NO: GRID REF  AS LAID SIGN OFF  ROUTE OF NOW MAN & APPARATUS AS NOIGHTED  DEPTH OF COMES OF NEW MAN  OP OTHER PLEASE STATE)  DEPTH OF COMES AT CONNECTION FONT TO EXISTING MAN (POINT T)  PART* AS LAID S DRAWING FULL AS LAID DRAWING	SERVICE O	RDER No:_	80138553	G	RID REF	TQ3257477
OPERATION No: GRID REF  AS LAID SIGN OFF  ROUTE OF NEW MAINS APPRANTUS AS ROICATED  DEPTH OF COVER OF NEW MAINS APPRANTUS AS ROICATED  DEPTH OF COVER AT CONNECTION POINT TO EXERTING MAIN (POINT 1)  OF OTHER PLEASE STATE)  PART' AS LAID'S DRAWING FULL AS LAID ORAWING	OPERATION No: GRID REF OPERATION NO: GRID REF  AS LAID SIGN OFF  ROUTE OF NEW MAPIN & PRIPARATUR AS INDICATED  DEPTH OF COMER OF NEW MAPIN  0.0 OTHER (PLEASE STATE)  DEPTH OF COMER AT CONNECTION POINT TO EXISTING MAN (POINT T)  0.0 OTHER (PLEASE STATE)  PART* AS LAID'S DRAWING FULL AS LAID DRAWING	OPERATION	N No:		G	RID REF	
OPERATION No: GRID REF  AS LAID SIGN OFF  ROUTS OF NEW MAINS A APPARATUS AS INDICATED  DEPTH OF COVER OF NEW MAIN  0.0 OTHER (PLEASE STATE)  DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAIN (POINT 1)  0.0 OTHER (PLEASE STATE)  PART' AS LAID'S DRAWING FULL 'AS LAID GRAWING	OPERATION NO: GRID REF  AS LAID SIGN OFF  ROUTS OF NEW MAINS APPARATUS AS INDICATED  DEPTH OF COMER OF NEW MAIN  0.0 OTHER (PLEASE STATE)  DEPTH OF COMER AT CONNECTION POINT TO EXISTING MAIN (POINT T)  0.0 OTHER (PLEASE STATE)  PART' AS LAID'S DRAWING FULL AS LAID DRAWING	OPERATION	N No:		G	RID REF	
AS LAID SIGN OFF  ROUTE OF NEW MAIN & APPARATUS AS PICICATED  BEPTH OF COMES OF NEW MAIN  0.9 OTHER PLEASE STATE)  DEPTH OF COMES AT CONNECTION FORM TO EXISTING MAIN (FOINT 1)  0.9 OTHER PLEASE STATE)  PART AS LAID'S DRAWING FULL AS LAID GRAWING	AS LAID SIGN OFF  ROUTE OF NEW MAIN & APPARATUS AS NORCATED  DEPTH OF COMER AT CONNECTION POINT TO EXISTING MAIN (POINT T)  OUT OTHER (PLEASE STATE)  PART* AS LAID S DRAWING FULL AS LAID DRAWING	OPERATION	N No:		G	RID REF	
ROUTE OF NEW MAINS A PPARATUS AS INDICATED  DEPTH OF COVER OF NEW MAINS  0.9 OTHER (PLEASE STATE)  DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAIN (POINT 1)  0.9 OTHER (PLEASE STATE)  PART AS LAID S DRAWING FULL AS LAID OPPARING	ROUTE OF NEW MAINS A PRANTUS AS NOICHTED  DEPTH OF COVER OF NEW MAIN  DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAIN (POINT 1)  DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAIN (POINT 1)  PART' AS LAID'S DRANNING FULL AS LAID DRAWING	OPERATION	N No:		G	RID REF	
ROUTE OF NEW MAINS A PPARATUS AS NOICATED  DEPTH OF COVER OF NEW MAINS  DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAIN (POINT 1)  DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAIN (POINT 1)  PART' AS LAID'S DRAWING FULL 'AS LAID' DRAWING	ROUTE OF NEW MAINS A PRARATUS AS NOICHAED  DEPTH OF COVER OF NEW MAINS  0.9 OTHER (PLEASE STATE)  DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAIN (POINT 1)  0.9 OTHER (PLEASE STATE)  PART' AS LAID'S DRAWING FULL' AS LAID DRAWING						
ROUTE OF NEW MAINS A PRIVAS TUS AS INDICATED  DEPTH OF COVER OF NEW MAINS  0.0 OTHER PILASE STATE)  DEPTH OF COVER AT CONNICTION POINT TO EXISTING MAIN (POINT 1)  0.0 OTHER PILASE STATE)  PART AS LAID'S DRAWING FULL'AS LAID ORAWING	ROUTE OF NEW MARK & RPHANATUS AS INDICATED  DEPTH OF COVER OF NEW MARK  0.0 OTHER (PLEASE STATE)  DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAIN (POINT T)  0.0 OTHER (PLEASE STATE)  PART AS LAID'S DRAWING FULL AS LAID DRAWING	AS LAI	D SIGN (	OFF_			
0.9 OTHER PLEASE STATE)  DEPTH OF COMER AT CONNECTION POINT TO EXISTING MAIN (POINT 1)  0.9 OTHER PLEASE STATE)  PART' AS LAID'S DRAWING FULL' AS LAID ORAWING	0.0 OTHER (PLEASE STATE)  DEPTH OF COMES AT CONSCICION FONT TO EXISTING MAN (POINT T)  0.0 OTHER (PLEASE STATE)  PART AS LAID S DRAWING FULL AS LAID DRAWING	ROUTE OF NEV	W MAIN & APPA	RATUS AS IN	DICATED		TEX TOOOHPING
DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAN (POINT 1)  0.9 OTHER (PLEASE STATE)  PART' AS LAID'S DRAWING PULL 'AS LAID DRAWING	DEPTH OF COVER AT CONNECTION POINT TO EXISTING MAN (POINT T)  0.9 OTHER (PLEASE STATE)  PART' AS LAID'S DRAWING FULL AS LAID DRAWING	DEPTH OF COV	VER OF NEW M	AIN:			
0.9 OTHER (PLEASE STATE)  PART 'AS LAID' S DRAWING FULL 'AS LAID' 'AS LA	0.9 OTHER (PLEASE STATE)						
PART ' AS LAID' S DRAWING FULL 'AS LAID' DRAWING	PART ' AS LAID' S DRAWING FULL 'AS LAID' DRAWING		0.9	OTHER	(PLEASE	STATE)	
							POINT 1)
		DEPTH OF CO	VER AT CONNE	CTION POIN	TO EXIST	ING MAIN (	POINT 1)
		DEPTH OF CO	VER AT CONNE	CTION POIN	TO EXIST	ING MAIN (	POINT 1)
F/H's PERMANENTLY REINSTATED YES NO NA NA	First PERMANENTLY REINSTATED YES NO NA NA	DEPTH OF CO	VER AT CONNE	CTION POINT	TO EXIST	ING MAIN ( STATE)	
		DEPTH OF CO	VER AT CONNE	CTION POINT	TO EXIST	ING MAIN ( STATE)	
CONTRACTOR SIGN OFF: DATE		DEPTH OF COMPART AS LAID	O.9 OPAWING	OTHER OTHER	TO EXIST	ING MAIN ( STATE)  AID DRAWI	NG N/A

PREFERRED LAYOUT FOR MAINS IN A 2 METRES WIDE FOOTW
NOTES:
THE LAYOUT OF MAINS IS GENERALLY IN ACCORDANCE WITH THE REPORT OF JOINT COMMITTEE ON LOCATION OF UNDERGROUND SERVICES PUBLISHED BY THE INSTITUTION OF CIVIL ENGINEERS.
2. THE DIMENSIONS SHOWN REPRESENT THE PREFERRED ARRANGEMENT IN STRAIGHT ROUTES ON RESIDENTIAL ESTATES. VARIATIONS MAY BE NECESSARY AT CURVES AND CHANGES OF GRADIENT.
3. THE SPACE ALLOCATED IS CONSIDERED TO BE THE ABSOLUTE MINIMUM AND IN CERTAIN CIRCUMSTANCES E.G. WHERE BOTH HY AND LY CABLE WILL BE LIAD IN THE ALTERNATIVE POSITION AND ADDITIONAL WIDTH MAY BE REQUIRED.
<ol> <li>WHERE SERVICES ARE TO BE CONNECTED TO MAINS A WINMUM DISTANCE OF ZOM IS REQUIRED BETWEEN THE BUILDING LINE AND THE CENTRE LINE OF THE MAIN.</li> </ol>
5. MINIMUM DISTANCE OF ANY WATER SERVICE TO ANY SURFACE/FOUL WATER STRUCTURE IS 300mm.
COVER OF WATER MAIN
UP TO 12"(300mm) 900mm 12"(300mm) TO 24"(800mm) 1100mm





TH: S:CAD DRAWINGS-CLEAN WATER 2014;50012516 AYLESBURY ESTATE REGEN SITE IS IC, WESTMORELAND ROAD, LONDON, SE17 2BY/Drawings



### **WSP UK Limited**

WSP House London WC2A 1AF UK

Tel: +44 020 7314 5000 Fax: +44 20 7314 5111 www.wspgroup.co.uk



# PRICE&MYERS

# Aylesbury Estate

Structural Engineer's Planning Report

Prepared by: Eleanor Ball Job Number: 22877

Date Version Notes / Amendments / Issue Purpose

August 2014 A Draft

### Contents

### 1 Introduction

### 2 Existing Development

- 2.1 Location and Surroundings
- 2.2 Existing Buildings
- 2.3 Ground Conditions
- 2.4 Demolition Statement

### 3 Proposed Development

- 3.1 Summary
- 3.2 Proposed Buildings
- 3.3 Building Types

### 4 Substructure

- 4.1 Foundation Scheme
- 4.2 Basements
- 4.3 Trees

### 5 Superstructure

- 4.1 Summary
- 4.2 Type A: Concrete Frame
- 4.3 Type B: Traditional Build

### 6 Design Criteria

- 4.1 Codes and Standards
- 4.2 Design Life
- 4.3 Loadings
- 4.4 Design Fire Periods
- 4.5 Disproportionate Collapse

### 7 Preliminary Drawings

### **Appendices**

Appendix A: Existing Buildings: Jespersen System

Appendix B: Existing Foundation Drawing

### 1 Introduction

Price and Myers have been appointed to provide structural guidance for the planning design of the First Development Site (FDS) of the Aylesbury Estate Masterplan.

The following report provides a discussion of the proposed structural design for the six new plots of residential accommodation and community facilities. The report will also discuss the existing site and the nature of the current buildings and ground conditions, and our expectations for the demolition and site clearance.

The structural scheme designs included in Section 7 are preliminary, with the purpose of defining the structural intent for architectural coordination and budget costing purposes. Fully designed structural designs will be developed for each of the buildings, as part of the tender design process.

# 2 Existing Development

### 2.1 Location & Surroundings

Aylesbury Estate is located to the south of Elephant and Castle in South East London. The masterplan area is shown by the red dashed line in Figure 1 with the First Development Site (FDS) located on the edge of Burgess Park.



Figure 1: Extent of Aylesbury Masterplan

# 2.2 Existing Buildings

In the FDS, there are ten buildings which vary in size and construction type. Eight of the buildings date from the 1970s and are of precast concrete large-panel construction using the Jespersen System. The existing buildings can be grouped into types as follows:

- 1. 4 storey Jespersen System
- 2. 5 storey Jespersen System 'court block'
- 3. 5 storey Jespersen System 'route block'
- 4. 13 storey Jespersen System
- 5. Arklow House
- 6. Ellison House

The location of these existing building types are shown on the site plan in Figure 2.



Figure 2: First Development Type building types.

The Jespersen System comprises precast concrete floor and roof panels spanning onto loadbearing, precast concrete cross-walls. The end walls to the blocks are storey high precast panels of sandwich construction. The long elevations are continuous window strips over single leaf precast concrete panels which span between the cross-walls.

In the low rise blocks (Types 1-3), ground to first floor is constructed from in-situ concrete with the precast concrete panel system starting at first floor. Access is provided by external walkways at second floor level which have precast concrete panels acting as the balustrading. These walkways connect to in-situ concrete bridges which allow access at second floor level to other blocks across the development.

In the 13 storey blocks (Type 4) ground to fourth floor is built using in-situ concrete and contains amenities, car parking and external walkways. Above fourth, residential accommodation is provided in the Jespersen System. Above the fourth storey, internal walkways are provided at every other level enclosed by ribbon glazing above the precast balustrade. The blocks are serviced by cores with lifts and precast concrete stairs. More detail of the Jespersen System building types can be found in Appendix A.

It is unknown what the foundations of the existing Jespersen buildings are, however, one drawing has been found which shows large concrete pads, Appendix B. We anticipate that this foundation solution will have been adopted for the low rise blocks (Types 1-3), however, it is likely that the Type 4 buildings will have piles. See Section 2.4.4 for a discussion of the ground works required.

Building Type 5 is Arklow House which is a pre-war, 5 storey masonry building providing residential accommodation only. It is expected that the construction is load bearing masonry walls with filler joist floors, however, due to restricted access we have been unable confirm this. A photo of Arklow House is shown in Figure 3.



Figure 3: The exterior façade of Arklow House.

Building Type 6 is Ellison House which is currently used as offices and a community building. The construction type is expected to be panellised precast concrete construction with ribbon windows however, due to restricted access we have been unable confirm this. Ellison House is connected to one of the 13-storey blocks via a concrete walkway at second floor level as shown in Figure 4.



Figure 4: Ellison House and connecting in situ walkway.

### 2.3 Ground Conditions

### 2.3.1 Summary

A preliminary ground investigation report has been produced by Soils Ltd in February 2013 (Report Number 13397/GIR). A number of intrusive investigations, testing and monitoring was carried out by Soils Ltd. The main soil types are as follows:

Topsoil/Made Ground (TS/MG)
Langley Silt Member (LASI)
Kempton Park Gravel Formation (KPGR)
Lambeth Group (LMB)
Thanet Sand Formation (TS)
White Chalk Subgroup (WHCK)

Ground water was found in the gravels in a number of locations across site. The site wide ground conditions encountered in the boreholes are summarised in Figure 5.

Table 2.2  Ground Conditions					
Strata	Age	Depth End (m l	ountered	Typical Thickness	Description
150.000.000.000		Тор	Bottom	(m)	-
TS/MG	Recent	GL	0.75* - 3.70	1.82	Concrete/Tarmac/Grass and silty clay with gravel overlying dark brown to brown, grey gravelly sandy silty clay and clayey sand and sandy gravel with brick/brick rubble, cement, ash, wood, shell, ceramic, glass and roots.
LASI	Pleistocene	0.80 - 2.65	1.90 – 4.5	1.34	Firm light to dark, orange brown, yellow brown, grey slightly gravelly slightly sandy clay with occasional ferruginous dark brown pockets. Gravel fine to medium angular to rounded.
KPGR	Pleistocene	1.90 - 4.50	5.50 - 7.30	4.04	Brown, orange brown gravelly sand and sandy clayey fine to coarse angular to rounded gravel with occasional sandy silty clay layers.
LMB	Palaeocene	5.5 – 7.30	9.80 - 11.00	3.76	Firm to stiff red grey brown mottled slightly gravelly slightly sandy silty clay and slightly gravelly clayey sand.
TS	Palaeocene	9.80 - 11.00	22.50 - 22.80	12.37	Dense grey and green grey silty sand.
WHCK	Upper Cretaceous	22.50 – 22.80	25.00*	Not Proven	The White Chalk Subgroup comprised structureless chalk, which was composed of off-white sandy gravelly clayey silt with occasional flint gravel. The chalk gravel was off-white, weak and of low to medium density.

Note - \*Full depth of borehole

Figure 5: Extract of ground conditions table from Soils Ltd Report 13397/GIR.

### 2.3.2 Foundations

The ground investigation report suggests that if a strip footing foundation solution is implemented then they must bear into the Kempton Park Gravels (KPGR) which are at a varying depth of 1.9-4.5m below ground level. In addition, the proximity of trees should be checked and the foundations designed to comply with NHBC Standards Chapter 4.2 and BRE Digest 240.

In reality, the proposed buildings in the development will not be suitable for strip footings due to the high foundation loads so instead it is suggested a pile solution is implemented. The ground investigation report recommends that a bored pile solution is adopted using temporary casing through the Made Ground (TS/MG) and Langley Silt Member (LASI). Preliminary bearing capacities

Page 7 of 38

have been provided for 450, 600 and 750 diameter bored piles down to a depth of 21m. These capacities have been used in the preliminary foundation design of the new buildings (refer to Section 4).

It is recommended that the ACEC (Aggressive Chemical Environment for Concrete Class) AC-1 should be adopted for concrete in the ground.

### 2.3.2 Ground Slabs

Due to the presence of Made Ground (TS/MG) across the site, it is suggested in the site investigation that suspended ground floor slabs are implemented. In our scheme design, we have provided suspended ground slabs to all blocks except for basement areas. We have assumed that in basements the excavation is deep enough to remove the Made Ground (MG/TS) and Langley Silt Member (LASI) and so a ground bearing slab will be acceptable.

The ground investigation report highlights the potential risk of shrinkable soils in the Lambeth Group (LMB). We do not predict that any structure, except piles, will be deep enough to be within the Lambeth Group (LMB) and so we have not specified heave protection in the scheme design. However, there is a risk that surface excavation may result in unloading of the Lambeth Group (LMB) resulting in heave and thus a requirement for heave protection on the structure above.

A specialist geotechnical consultant, such as Soils Ltd, needs to advise on the assumption that ground bearing slabs can be used below the Langley Silt Member (LASI) and also, confirm whether heave due to unloading should be protected against. This work can may require further testing of the clays.

### 2.3.2 Ground Water

Ground water was found during the intrusive investigation in a number of locations across site at depths varying between 4.7 and 8.2m below ground level. This generally falls in the Kempton Park Gravel Formation (KPGR) and Lambeth Group (LMB).

The 'lost rivers of London' map, Figure 6, shows that a historical river runs along Albany Road which is immediately south of the site. It is not anticipated that ground water level will be within the excavation depths, however, levels are subject to vary due to seasons so may be found at higher levels than anticipated.




Figure 6: Extract from 'lost rivers of London' map

#### 2.3.2 Contamination

In Section 5 of the Soils Ltd report, extensive testing and sampling of the ground and ground water is summarised. A variety of contaminants are found in the samples and so ground remediation and capping strategies are recommended as well as further testing and sampling following site strip.

The results for gas monitoring are to be issued as an addendum to the report which we have not yet received. At the time of writing, it is unknown if requirements for gas ventilation is required and so, this has not been allowed for in our scheme design. Should gas be present then it is likely that a gas membrane and ventilation of the void below ground would be required under all the ground floor slabs. This would mean that the basement slabs, currently considered ground bearing, would have to become suspended.

### 2.4 Demolition Statement

A detailed method statement and phasing plan from a specialist demolition contractor who will be carrying out the works will be required. It is expected that this report will cover in detail the Health, Safety and Environmental considerations associated with the demolition of the FDS as well as demonstrating compliance with any Demolition Planning Permission Conditions in place.

The following statement is an indicative methodology for the building's demolition only and shall not replace the specialist sub-contractors method statement.

### 2.4.1 Existing Documentation

There are four reports which provide information about the buildings constructed using the Jespersen System, three are structural reports commissioned by the London Borough of Southwark. The reports available are as follows:

- 1. 1965: Original design proposal and approval.
- 2. 1997: Jenkins & Potter Consulting Engineers; Structural appraisal of current degradation of large panel buildings and advise on future maintanence and repair.
- 3. 2002: Frederick Snow & Partners; Structural appraisal of existing large panel buildings including testing and structural review of propsed alterations.
- 4. 2005: Conisbee Consulting Engineers; Large panel buildings robustness and disproportionate collape review.

We have not been able to source any existing drawings except those in the aforementioned reports. One drawing is of particular interest as it shows a foundation scheme for one of the long blocks, probably the 5-story 'route block' or similar. This drawing is in Appendix B.

### 2.4.2 Pre-Demolition

A period of pre-demolition works will be required including enabling works, soft-strip, asbestos removal and post-strip works.

Enabling works are expected to include the erection of site hoarding; set up of site welfare facilities and supply of temporary building services; environmental clean of the properties and site; removal of landscaping items such as bollards, fencing, garden walls and the like and; removal of trees and installation of tree protection measures.

Pre-strip works are expected to include removal of loose furniture and fittings from the properties; strip of built in kitchens and heating systems; removal of remaining building services such as water tanks and electricity and gas meters.

It is expected that a site wide asbestos survey will be carried out and that specific method statements will be written for the removal of asbestos by a specialist sub-contractor. Approval of these method statements will be required by the Health and Safety Executive prior to commencement. It is expected that exclusion zones, air testing and specialist waste disposal will be explained in detail in the method statements.

Post-strip works are anticipated to comprise window and glazing removal; non-structural elements and remaining floor finishes.

### 2.4.3 Demolition Works

From the Conisbee Report (2005) it can be concluded that buildings above six storeys are expected to have been constructed with suitable robustness detailing to prevent progressive collapse. Buildings below six stories (Building Type 1, 2, 3, 5 and 6 from Figure 2) are anticipated not to have been constructed with any vertical or horizontal ties and thus will be susceptible to the "stack of cards" effect during demolition. It is therefore expected that a combination of techniques will be implemented including local dismantling/deconstruction and the use of high reach demolition equipment.

Dismantling/deconstruction is the controlled removal of small sections of structure whilst employing protection and temporary support of the remaining building. Demolition is the tearing down of structure.

A number of the existing buildings including both 13 storey blocks and Ellison House are located very close to site boundary and so full height scaffolding will be required to protect the public. It is recommended that this scaffold will be tied back to the structure and fully sheeted.

Dismantling/deconstruction works may include:

- Installation of temporary back propping of precast floor panels and bracing of precast crosswalls.
- Gradual removal of floor and walls by mini-excavators supported on back propped floors.
- Removal of debris to ground level via mobile crane where it can be safely crushed as required for waste disposal or recycling.

It is suggested that the dismantling will occur in a sequence similar to that of construction and will take the form of a pyramid, stepped down on a floor by floor basis. The dismantling technique could be used for the upper storeys of the 13 storey blocks to bring them down to an acceptable height for the use of the demolition equipment.

Demolition works may include:

- Use of a high reach demolition rig equipped with a hydraulic crusher on the machine arm.
- Noise and dust levels will require control and monitoring. Potentially the use of a water jet on the end of the machine arm could be implemented.

We anticipate that this demolition technique will be used for all buildings under 6 storeys as these structures are expected to have no inherent robustness and will create an unsafe, working environment for operatives once demolition has commenced. It can also be used for the large 13 storey blocks once they have been dismantled to a height within the reach of the demolition rig.

### 2.4.4 Ground Works

From the drawing in Appendix B it can be seen that the existing buildings up to 5 stories are likely to be founded on large mass concrete pad foundations, however, the depth is unknown. The foundation scheme for the taller 13 storey blocks is unknown but anticipated to be piled foundations.

Due to the extensive coverage of existing buildings and services across the development, we expect that site clearance will require the breaking out and excavation of all existing foundations down to a level equal to the base of the existing pad foundations or to the underside of new pile caps, whichever is greater. It is likely that pile probing will be required site wide, particularly under the 13 storey blocks, however this should be reviewed following excavation.

# 3 Proposed Development

### 3.1 Summary

The proposed development covered in the FDS has been split into six units with different building uses and massing in each. The development is connected by new infrastructure between the units and break-out spaces within the units.

A description of each block is provided in Section 3.2. Figure 7 provides a layout plan for the new blocks.




Figure 7: Layout of the proposed buildings in the FDS.

# 3.2 Proposed Buildings

### 3.2.1 Block 1

Block 1 provides a mixture of accommodation including a community centre, an extra care facility for the elderly, a number of residential flats and maisonettes. The ground floor accommodation is predominantly extra care facilities such as living and dining space; the community centre, which occupies a double height space, and the maisonettes. The majority of the building is seven storeys high and occupied by the extra care facility. The block is a U-shape with a tower located on each end. The towers accommodate the residential flats and do not exceed 10 storeys.

A key design feature of Block 1 is the façade which incorporates 1 and 2 storey arches. It is proposed that these elements are formed in pre-cast concrete to obtain a high quality finish.

#### 3.2.2 Block 2 and 3

Block 2 and 3 predominantly comprise four storey terrace housing with private gardens in the centre. On the end of each terrace a 4-6 storey building provides accommodation for offices and community services.

#### 3.2.3 Block 4

Block 4 provides high density residential accommodation with car parking at ground floor level and a first floor podium slab supporting a community open space. The tallest tower reaches 20 storeys with the lowest section being 6 storeys. A basement is provided under the tower which provides plant space. Space for surface water attenuation is provided in the form of a shallow basement under the car parking.

There is a double height entrance area provided a ground floor level underneath the 20 storey tower. To provide a column free space in the entrance atrium, large transfer structures are required below the second floor slab.

### 3.2.4 Block 5

Block 5 is very similar to Block 4 but with an 18 storey tower.

### 3.2.5 Block 6

Block 6 is similar to Blocks 4 and 5, however, it does not include car parking at ground floor level and therefore no podium slab is provided. The ground floor accommodation is predominantly two storey maisonettes over which the accommodation changes to flats. The tallest tower reaches 16 storeys with the lowest section being 7 storeys. A basement may be provided under the tower to provide plant space, however, no attenuation storage is required. The gas pressure reduction system will be housed in a separate, single storey building on the plot of Block 6.

### 3.3 Building Types

For the purpose of Section 4 and 5 of this report, it will be considered that there are two types of building on the proposed development.

Type A: High density residential accommodation and community facilities of 4 or more storeys.

Type B: Terraced housing of 4 or less storeys.

### 4 Substructure

### 4.1 Foundation Scheme

In section 2.3.2, the foundation options are discussed and it is concluded that for the proposed development a piled solution is most suitable. In the ground investigation report by Soils Ltd it is suggested that a bored pile solution is adopted using temporary casing through the Made Ground and Langley Silt Member. Preliminary bearing capacities have been provided for 450, 600 and 750 diameter bored piles down to a depth of 21m. These capacities have been used in the preliminary foundation design of the new buildings.

For the Type A buildings, the majority will be supported on 3-pile caps using 750 diameter piles. Under cores and the towers, it is likely that a piled raft solution will be required due to the large loading requirements. These piles will be designed to resist both the vertical and lateral loading induced from winds.

For the most part, we have suggested the pile caps sit below a suspended reinforced concrete ground floor slab. In the attenuation tanks, we propose that the pile caps are cast above ground with a reinforced concrete ground bearing slab between pile caps, however, this is subject to confirmation that gas protection is not required.

For the Type B buildings, a bored pile solution is also proposed, supporting reinforced concrete ground beams. It is expected that the ground beams will support either a suspended reinforced concrete slab or a beam and block floor at ground level.

### 4.2 Basements

We have allowed for basements under the towers on Block 4, 5 and 6 to house a plant room and under Blocks 4 and 5 podiums to house attenuation tanks. The site is large enough to permit open excavation, however, due to the expected instability of the Made Ground and Langley Silt Member, we anticipate the excavation for these basements will require battering back to a minimum 45° angle or cut in 1,2m high steps. This will need to be assessed by the ground works contractor as part of their risk and method statement.

### 4.3 Trees

There are a number of trees on the current development which will be removed during the enabling works and replaced by new trees following construction. An analysis of the new structures in relation to new and removed trees will be carried out pre-tender. As a piled solution is to be adopted, it is not expected that protection or deepening of foundations will be required, but this must be confirmed by a geotechnical specialist consultant.

# 5 Superstructure

### 5.1 Summary

The following section will discuss the superstructure options for both building types separately.

### 5.1.1 Type 1

Large buildings such as these lend themselves to either a steel or concrete frame construction. Both timber and load bearing masonry may also be considered, however, above six storeys the wall build-up for a load bearing masonry frame becomes very thick, whereas the stability and global movement of a timber building becomes critical.

Through scheme design it has become apparent that the proposed buildings do not lend themselves to a regular grid due to the mixture of uses and accommodation types throughout their height. In addition, the client is keen to minimise floor to floor heights which have a significant impact when the blocks rise up 20 storeys. For these reasons we have provided scheme design using a reinforced concrete solution with flat slabs. The flats slabs allow for minimum floor depths, flexibility for building services distribution and a degree of flexibility in column locations.

The initial scheme design, which is discussed in more detail in Section 5.2, is based on the use of traditional reinforced concrete cast in-situ. Alternatively, a post-tensioned concrete solution would be suitable and may offer a small saving in slab thickness. There is also the option of a hybrid construction where some or all of the vertical elements become precast concrete. If in-situ concrete is maintained, then there is the option to use pre-rolled, fabric reinforcement which has been found to provide large programme savings during construction. These decisions would be led by the main contractor in discussion with the design team at a later stage in the project.

### 5.1.2 Type 2

For the terrace houses, three construction methods have been explored which are: concrete frame, cross laminated timber and traditional load bearing masonry. Whilst all options are feasible, the traditional build has been chosen as the preferred option.

### 5.2 Type A: Concrete Frame

### 5.2.1 Frame

#### Slabs:

There are a number of aspects affecting slab design which need to be considered:

- Loadings
- Span (distance between columns and walls)
- Thickness
- Quantity of reinforcement
- Size of columns

Assuming a consistent loading and column size, the distance that the slab can span is dependent on both the quantity of reinforcement and the overall thickness of the slab. In buildings of complex

shape, such as those in the new development, it is an iterative process to find the optimum slab thickness and column layout.

For the purpose of scheme design, we have carried out the analysis of a typical floor plate from Block 4. It can be concluded that, to limit overall slab deflection to the values set in Eurocode 2 for concrete design (which recommends span/250), a 250mm thick slab is able to span up to 6.5m and a 300mm slab is able to span up to 7.5m.




Figure 8: Slab anaylsis of Block 4

In our scheme design drawings provided in Section 7, a 250mm slab depth has been adopted for all Type A buildings and so the column layout has been arranged to reduce spans to 6.5m or less. Should a 300mm slab be adopted at a later stage of the design, the column layouts could be reconfigured, however, the overall height of the building would increase by 50mm per floor. For the 20-storey towers this is equivalent to 1m increase in building height and so the costs associated with the additional cladding will need to be considered.

### Columns:

As a concrete solution has been adopted, there is a degree of flexibility in the section shape which can be used for the columns, however, the minimum dimension of a column is limited by the design code for protection against fire. Typically, the minimum thickness that can be achieved for 60 minute fire rating is 200mm, however, this requires the column to be 800 long.

In the FDS, the majority of blocks are 6/7 storeys high, however, there are towers up to 20 storeys in Blocks 4 and 5. Taller blocks require larger columns at lower levels but it is possible to reduce the section size up the building.

As part of our scheme design, we have provided a preliminary column layout for each block to allow sufficient space in the Architectural layouts for the structure. A combination of rectangular and square columns have been used which will be refined in later stages of the design process.

In Block 1, the majority of edge columns at ground and first make up the feature arched façade. In order to achieve the high quality finish desired, it is proposed that these columns will be precast concrete. It is possible that not all of these columns will be required structurally and thus some may

be "dummy" columns for aesthetic use only. If the columns are incorporated into the structure to make it a hybrid construction, then there will need to be a thermal break between the internal and external structure to prevent cold bridging.

### Roof:

Generally, green roofs have been specified throughout the development, however, these will only be accessible at the top of the towers. To allow for the higher loading caused by a green roof a 350mm slab has been provided.

Where the roof is accessible, the architectural scheme provides storey high, cantilevered walls around the building perimeter. A hot rolled steel frame will be required to provide lateral restraint to this wall. In some locations, for example in Block 1, this steel frame extends across the roof garden to act as a pergola. The steel frame will be connected back to the roof slab using a thermal break to prevent cold bridging.

It is assumed that plant will not be stored at roof levels, but instead will be placed internally in the basement or ground floor areas provided.

#### Podium Slabs:

In Blocks 4 and 5, the first floor slab acts as a podium over the car park and will support communal landscaping. The location of columns supporting the podium slab will be dictated by the car park layout which means the slab must be capable of spanning long distances (currently expected to be up to 9m). The slab will need to incorporate voids for the ventilation of the car park space and support areas of deep planters for trees in the landscaping scheme. For these reasons, the podium slab will be in the order of 450mm deep.

It is important to consider the impact the slab thickness and landscaping build up will have on the floor to floor heights at ground floor level of Block 4 and 5. Figure 9 shows an indicative section through the transition from external podium level and the internal residential areas. It can been seen that the internal slab needs to be set at a higher level than the podium slab, in order to allow for flush finishes at thresholds. We expect that the car parking will be unheated space and so the thermal line of the structure at this interface will need to be considered carefully.




Figure 9: Section through the podium slab showing interface between external and internal.

#### Transfer structures:

In Blocks 4 and 5, there is a double height entrance at ground floor level. The columns in the residential layouts above second floor do not align with the columns in the entrance below. It is proposed that transfer beams in the order of 1.5m deep are provided at second floor level to support the residential columns above. Figure 10 indicatively shows the proposal.




Figure 10: Indicative structural scheme for double height entrances in the towers of Blocks 4 and 5

During scheme design, it has been recommended that the floor to ceiling heights remain consistent between blocks and so, columns layouts which avoid transfer structure have been assumed. It is likely that during the next stage of design, areas will be identified where transfer structure is unavoidable in order to work with the architectural layouts. We expect that transfer beams will be required and will be in the order of 750-1200 deep depending on their location. The effect of this would be a difference in floor to floor heights between blocks, increased building heights and the associated costs. It is preferable to avoid transfer structure, if possible.

### 5.2.2 Stability and Movements


In the structural proposals, the stability of the buildings is provided by reinforced concrete walls around stair and lift cores. Where required, discrete concrete shear walls have been provided to provide additional restraint, for example, at the end of wings. These walls, typically expected to be 250mm thick, run continuously from ground level to roof and transfer the horizontal loads to the foundations.

In some blocks a movement joint has been provided to split the structure to a suitable size to allow for movements due to the thermal effects in the concrete. Figure 11 shows the typical layout of the shear walls and the indicative location of a movement joint in the podium slab.



Figure 11: Typical Block stability and movement system.

In the tower blocks, stability is critical and so we have carried out preliminary structural analysis to estimate the twist and deflection due to wind loads. We have provided a concrete wall in addition to the lift and stair core which reduced the deflections to an acceptable limit in accordance with Eurocode 2 for concrete design. Figure 12 shows the predicted deflected shape of the tower due to the wind loads. Further detailed analysis will be required in future design stages.






Figure 12: Preliminary structural deflection analysis of tower blocks

### 5.2.3 Balconies

All Type 1 blocks incorporate balconies and terraces which are either inset to the building footprint or pop-outs from the façade. Typically, we have suggested that the balconies will be constructed from in situ concrete with a thermal break along the building edge. However, we have assumed that the balconies will support only a light weight balustrade on the end of the cantilever and will be 2m or less in length. Within these constraints, the design intent is for the balcony slab to be 200 thick allowing a step down from the internal 250mm slab to incorporate the external finishes.

A similar philosophy could be adopted for terraces (external areas over inhabitable space), however, because the external build-up requires insulation, a greater external build up is required. This can be accommodated by stepping the soffit of the slab under terraces, however, this reduces the floor to ceiling height below. Figure 13 shows a section though a typical balcony and terrace.

Alternative options to explore are bolt-on steel frame or precast concrete balconies. In both instances, a thermal break will be required where fixing back to the concrete frame.




Figure 13: Typical sections through balcony and terrace slabs.

### **5.2.4 Stairs**

Generally, it is assumed that the main communal stairs will be constructed in precast concrete which will be supported back to the structural frame on steel angles.

We have assumed that private staircases within units are of lightweight steel or timber construction.

### 5.2.5 Walls

For the purpose of preliminary structural design, we have assumed that all internal partitions are of light weight construction, for example, 'Metsec' or the like. If blockwork walls were chosen then we would need to review the slab thickness to allow for the additional loading.

We have been advised that the external walls will comprise a single skin masonry outer leaf, 50mm cavity, 140 Kingspan insulation, 100 Metsec or other lightweight internal leaf and plasterboard. We expect that the external skin will be supported by a masonry hanger off the slab at every other level. An alternative option would be to provide brick slips instead of a full outer brick. Similarly, if a heavier build up was adopted, the slab thickness would require review.

### 5.3 Type B: Traditional Build

### 5.3.1 Frame

#### Floors:

The partitions within the terrace houses do not stack up between levels and so vertical support has to be taken from the party walls only. The width of one house is approximately 5.5m which is too far for a traditional timber joist. For this reason, it is suggested that engineered timber joists are used for the floor construction of the upper levels of the houses. Generally, the timber joists will span between party walls, however in some instances, for example around stair voids, steel beams may be required. The steel beam will be within the depth of the joists which are expected to be 300mm deep.

Building services will be able to run with the joist depths either alongside the joists or through slots in the joist web. These openings will require coordination at a later stage in the design process.

### Walls:

External walls are expected to comprise a minimum 100mm internal blockwork skin, 100mm cavity and insulation to architects requirements and a single brick outer skin. Party walls between the houses are assumed to be two skins of 100mm blockwork with a cavity between them for acoustic separation. These build ups are shown in Figure 14. Internal partitions are expected to be timber stud.




Figure 14: Typical wall build ups for terrace house.

### 5.2.2 Stability and Movements

Stability for each house will be provided by the blockwork party walls and a dedicated bracing wall at each level. The timber floors will be designed to act as diaphragms to transfer the lateral loading. The bracing wall could be constructed from 100mm blockwork if it continually aligns at every floor, or it could be timber stud as shown in Figure 15.




Figure 15: Typical bracing wall build up for terrace house.

The masonry and blockwork walls will need to be detailed to allow for building movements as noted in Figure 14. Around windows and door openings, it is likely that steel wind posts will be required to resist lateral loading. A typical wind post detail is shown in Figure 16.




Figure 16: Typical bracing wall build up for terrace house.

# 6 Design Criteria

### 6.1 Codes and Standards

Loadings to be assessed in accordance with:

BS EN 1991-1-1:2002
BS EN 1991-1-3:2003
BS EN 1991-1-4:2003
Structural design in accordance with:

BS EN 1991-1-1:2003

BS8500

BS EN 1993-1-1:2005 BS EN1996-1-1:2005 BS EN1995-1-1:2004

# 6.2 Design Life

50 years

# 6.3 Loadings

In scheme design, we have assumed the following loadings (all in kN/m<sup>2</sup>):

Residential	Permanent	Variable
Floor finishes 75mm screed Kingspan K3 insulation Ceiling & services Imposed load Partitions	0.25 1.8 0.05 0.3	1.5 1.0
Total superimposed	2.4	2.5
Podium slab - planted areas	Permanent	Variable
Podium slab - planted areas  Sedum mat 800mm soil Ceiling & services Drainage Void former Imposed load Trees	Permanent  0.3 16.0 0.5 0.5 0.1	Variable 3.0 2.5

Roof Garden - planted areas	Permanent	Variable
Sedum mat 800mm soil Ceiling & services Drainage Void former Imposed load Trees	0.3 16 0.5 0.5 0.1	3.0 3.0
Total superimposed	18.3	6.0

## 6.4 Design Fire Periods

Typically the fire rating is to be one hour. Concrete slabs, walls and columns minimum cover and dimensions to BS EN 1992-1-1:2004 will be specified. Higher fire resistance may be required to plant and substation areas.

#### 6.5 Disproportionate Collapse

Type A buildings are class 2B structures as required by the building regulations. Effective horizontal and vertical ties will be provided in all supporting columns and walls.

Type B buildings are class 2A structures as required by the building regulations. Effective horizontal ties, or effective anchorage of suspended floors to walls will be provided.


# 5 Design Drawings

[TO BE ADDED]

Appendix A

Existing Buildings: Jespersen System

There are four types of large panel construction buildings on the existing site which were constructed using the Jespersen System. These are labelled in the following figure:



There are four reports which provide information about these structures, three are structural reports which have commissioned by the London Bourough of Southwark. The reports available are as follows:


- 5. 1965: Original design proposal and approval.
- 6. 1997: Jenkins & Potter Consulting Engineers; Structural appraisal of current degradation of large panel buildings and advise on future maintanence and repair.
- 7. 2002: Frederick Snow & Partners; Structural appraisal of existing large panel buildings including testing and structural review of propsed alterations.
- 8. 2005: Conisbee Consulting Engineers; Large panel buildings robustness and disproportionate collape review.


### Type 1: 4 storey

There are two types of 4 storey buildings: with and without garages at ground level. The following pages give typical layouts of the 4-storey blocks extracted from the original design proposals and approval report.













4 STOREY + GARAGE









4 STOREY - GARAGE


### Type 2: 5 storey Court Block


The following photograph shows a typical 5 storey court block. The storey high precast concrete panels which make up the end wall can clearly be seen as well as the precast concrete cross-walls, slabs, balustrades and external walkways. In the background, there in an example of an in-situ concrete walkway which links the buildings at second floor level.




The following figure gives the typical layout of the 5-storey court blocks extracted from the original design proposals and approval report.















5 STOREY COURT BLOCKS


### Type 3: 5 storey Route Block


The following photograph shows a typical 5 storey route block. The second floor external walkway can be clearly seen with the precast balustrade. At ground level, the in-situ concrete garages can be seen. In the foreground, there in an example of an in-situ concrete walkway which links the buildings at second floor level.




The following figures give typical layout of the 5-storey route block extracted from the original design proposals and approval report.









5 STOREY ROUTE BLOCKS


### Type 4: 13 Storey Block

The following photograph shows a typical 13 storey block. It can be seen that the first four storeys which contain car parking and amenities are constructed in in-situ concrete. Above fourth floor the Jespersen System begins and the walkways become internal. The photo shows two cores, however, there are three in total on this block.




The following figures give typical layout of the 13-storey blocks extracted from the original design proposals and approval report.

AYLESBURY ESTATE



Appendix B

**Existing Foundation Drawing** 



AYLESBURY ESTATE FIRST DEVELOPMENT SITE - PHASE 1B / 1C BACK UP INFORMATION FOR EIA OVERVIEW SCHEDULE of CONSTRUCTION VEHICLE MOVEMENTS AND OPERATIVES ON SITE (EXCLUDES DEMOLITION) 2016 to 2021 J F M A M J J A S O N D J F M A M J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D D D F M A M J J A S O N D J F M A M J J A S O N D Month No Phase 1B/C : Plot 1 150 250 250 275 275 275 300 300 325 400 400 500 500 450 450 400 400 400 150 Vehicle movements 6450 50 60 60 60 70 70 70 100 100 100 120 130 130 110 100 90 80 70 60 Average number of operatives on site 88av Phase 1B/C : Plot 2 Vehicle movements 1500 Average number of operatives on site 25av Phase 1B/C : Plot 5 11450 Vehicle movements Average number of operatives on site 119av Phase 1B/C: Plot 6 9750 Vehicle movements 102av Average number of operatives on site Phase 1B/C : Plot 3 80 90 100 110 120 120 120 120 130 150 150 140 130 120 120 100 50 1950 Vehicle movements 20 22 25 25 25 30 30 35 35 40 40 40 40 40 30 30 20 Average number of operatives on site 31av Phase 1B/C : Plot 4 Vehicle movements 10800 50 60 80 80 80 100 100 110 115 120 120 120 120 120 140 140 175 140 140 120 120 120 120 100 112av Average number of operatives on site Phase 1B/C : Residual woks Vehicle movements 50 50 100 20 20 20av Average number of operatives on site Based upon a total of 50 vehicle movements per apartment (or equivalent). Based upon a total of 55 man weeks per apartment (or equivalent). Calculation for Plot 1 ~ Calculation for Plot 5 ~ Calculation for Plot 3 ~ 42 + 29 + 50 + 8 ( allowance for community ) = 129 units equiv. Energy Centre ( 10 equiv ) + 96 + 1 + 122 = 229 10 + 23 + 6 = 39 units 50 x 129 = 6450 vehicles. 6450 / 81 = av 80 per week / 347 per month 50x229=11,450 vehicles 11450 / 106 weeks = 467 / month av. 50 x 39 = 1950 vehicles 1950 / 70 weeks = 121 / month av. 55 x 129 = 7095 man weeks. 7095 / 81 = av 88 operatives on site. 55x229=12,595 man weeks 12595 / 106 = av 119 operatives on site. 55 x 39 = 2145 man weeks 2145 / 70 = av 31 operatives on site. Calculation for Plot 2 ~ Calculation for Plot 6 ~ Calculation for Plot 4 ~ 30 units 80 + 2 + 113 = 195 units 49 + 48 + 119 = 216 50x30=1500 vehicles 1500/66weeks = 98 / month av. 50 x 195 = 9750 vehicles 9750 / 105 weeks = 402 / month av. 50 x 216 = 10800 vehicles 10800 / 106 weeks = 441 / month av. 55x30=1650 man weeks 1650/66 = av 25 operatives on site. 55 x 195 = 10725 man weeks 10725 / 105 = av 102 operatives on site. 55 x 216 = 11880 man weeks 11880 / 106 = av 112 operatives on site.